



3 4456 0454257 3

ORNL/TM-13005

ornl

OAK RIDGE NATIONAL LABORATORY

LOCKHEED MARTIN




Report of the ANS Project Feasibility Workshop for a High Flux Isotope Reactor- Center for Neutron Research Facility

F. J. Peretz
R. S. Boeth

July 1995

OAK RIDGE NATIONAL LABORATORY
CENTRAL RESEARCH LIBRARY
CIRCULATION SECTION
4500N ROOM 175
LIBRARY LOAN COPY
DO NOT TRANSFER TO ANOTHER PERSON
If you wish someone else to see this
report, send in name with report and
the library will arrange a loan.
WON7989(12/77)



Advanced Neutron Source

MANAGED AND OPERATED BY
LOCKHEED MARTIN ENERGY RESEARCH CORPORATION
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ORNL/TM-13005

406

REPORT OF THE
ANS PROJECT FEASIBILITY WORKSHOP FOR A
HIGH FLUX ISOTOPE REACTOR-CENTER FOR NEUTRON RESEARCH FACILITY

December 12-16, 1994

Compiled by F. J. Peretz and R. S. Booth

Date published: July 1995

Prepared by
Oak Ridge National Laboratory
Oak Ridge, Tennessee 37831
managed by
LOCKHEED MARTIN ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

LOCKHEED MARTIN ENERGY RESEARCH LIBRARIES



3 4456 0454257 3

CONTENTS

| | |
|--|-----|
| LIST OF FIGURES | v |
| LIST OF TABLES | vii |
| ACRONYMS | ix |
| 1. REASONS FOR THE WORKSHOP | 1 |
| 2. PURPOSE AND SCOPE OF THE WORKSHOP | 3 |
| 2.1 PURPOSE | 3 |
| 2.2 REQUIREMENTS AND ASSUMPTIONS | 3 |
| 2.3 APPROACH | 4 |
| 3. THE HFIR-CNR FACILITY | 5 |
| 3.1 GENERAL SITE AND BUILDINGS | 5 |
| 3.2 SUMMARY SYSTEM DESCRIPTIONS | 8 |
| 3.2.1 Reactor, Reactor Cooling System, and Containment | 8 |
| 3.2.2 Beam, Instrument, Irradiation, and User Support Facilities | 9 |
| 3.2.3 Plant Systems | 10 |
| 3.3 COST ESTIMATE | 10 |
| 3.4 SCHEDULE FOR CONSTRUCTION | 11 |
| 3.5 METHOD OF ACCOMPLISHMENT | 11 |
| 4. REFERENCES | 14 |
| Appendix A. COMPARISON OF THE HFIR-CNR AND ANS FACILITIES | A-1 |
| Appendix B. HFIR-CNR COSTS BY WBS AND FUNDING TYPE | B-1 |
| Appendix C. HFIR-CNR SCHEDULE | C-1 |
| Appendix D. SCIENTIFIC INSTRUMENTS | D-1 |
| Appendix E. PRINCIPAL CONTRIBUTORS | E-1 |

FIGURES

1. A layout for the High Flux Isotope Reactor-Center for Neutron Research site 6
2. A layout of the guide hall of the High Flux Isotope Reactor-Center
for Neutron Research 7

TABLES

1. Total project cost for High Flux Isotope Reactor-Center for Neutron Research 12
2. Total project cost for the High Flux Isotope Reactor-Center for Neutron Research
heavy water upgrade and detritiation facility 12
3. Annual operating costs for High Flux Isotope Reactor-Center for Neutron Research
and for the heavy water upgrade and detritiation facility 13

ACRONYMS

| | |
|----------|---|
| ANS | Advanced Neutron Source |
| CDR | conceptual design report |
| DOE | Department of Energy |
| HFIR | High Flux Isotope Reactor |
| HFIR-CNR | High Flux Isotope Reactor/Center for Neutron Research |
| ORNL | Oak Ridge National Laboratory |
| PIDAS | perimeter intrusion detection and assessment system |
| REDC | Radiological Engineering Development Laboratory |
| SANS | small angle neutron scattering |
| WBS | work breakdown structure |

1. REASONS FOR THE WORKSHOP

The Advanced Neutron Source (ANS) Conceptual Design Report (CDR) and its subsequent updates provided definitive design, cost, and schedule estimates for the entire ANS Project.^{1,2*} A recent update to this estimate of the total project cost for this facility was \$2.9 billion, as specified in the FY 1996 Congressional data sheet, reflecting a line-item start in FY 1995.

In December 1994, ANS management decided to prepare a significantly lower-cost option for a research facility based on ANS which could be considered during FY 1997 budget deliberations if DOE or Congressional planners wished. A cost reduction for ANS of about \$1 billion was desired for this new option.

It was decided that such a cost reduction could be achieved only by a significant reduction in the ANS research scope and by maximum, cost-effective use of existing High Flux Isotope Reactor (HFIR) and Oak Ridge National Laboratory (ORNL) facilities to minimize the need for new buildings. However, two central missions of the ANS—neutron scattering research and isotope production—were to be retained.

The title selected for this new option was High Flux Isotope Reactor-Center for Neutron Research (HFIR-CNR) because of the project's maximum use of existing HFIR facilities and retention of selected, central ANS missions. Assuming this shared-facility requirement would necessitate construction work near HFIR, it was specified that HFIR-CNR construction should not disrupt normal operation of HFIR.

Additional objectives of the study were that it be highly credible and that any material that might be needed for U.S. Department of Energy (DOE) and Congressional deliberations be produced quickly using minimum project resources. This requirement made it necessary to rely heavily on the ANS design, cost, and schedule baselines. A workshop methodology was selected because assessment of each cost and/or scope-reduction idea required nearly continuous communication among project personnel to ensure that all ramifications of proposed changes were properly considered.

* ANS provided the full research capability requested by the scientific community as specified in the Seitz-Eastman report, repeated reports from the Basic Energy Sciences Advisory Committee, the Kohn panel, and the National Steering Committee for the Advanced Neutron Source. The ANS design maximized performance of the research tool; that is, it provided the highest flux possible to the scientific instruments and facilities, while still meeting safety and availability requirements. Also, ANS was an entirely new facility located near but not dependent on the existing HFIR facility.

2. PURPOSE AND SCOPE OF THE WORKSHOP

2.1 PURPOSE

A primary purpose of this study was to provide a feasible design, schedule, and cost estimate for the HFIR-CNR that meets the assumptions and requirements in Sect 2.2. Results reported here may be used for comparison with a later, more detailed conceptual design and associated, bottom-up cost and schedule estimate.

2.2 REQUIREMENTS AND ASSUMPTIONS

The central mission of the ANS was retained. That is, HFIR-CNR should be a world-class neutron research facility that could support hundreds of "small science" users annually. It should provide a smooth and successful transition of research capabilities now present at HFIR and the High Flux Beam Reactor at Brookhaven National Laboratory. In addition, HFIR-CNR should represent a premier center for research using neutron beams, as well as for research using slow positron and radioactive ion beams. Specific requirements for research capabilities included the following:

- The world's most powerful source of steady-state cold neutron beams derived from a high-powered research reactor.
- Unique capabilities for thermal neutron research using supermirror guide systems.
- Production capabilities to meet the national need for ^{252}Cf , a portable neutron source with many industrial, medical, and security applications.
- A high-flux facility for materials irradiation studies.
- Hydraulic tube facilities for the production of key medical and industrial isotopes.
- Activation analysis facilities with an unprecedented thermal neutron flux.
- A positron research facility with a positron beam intensity substantially greater than any other available in the world.
- The necessary support facilities and staff to serve as a true user facility.

In addition to those requirements, some baseline assumptions were established. All costs were estimated from those presented in the ANS FY 1996 Congressional data sheet. Cost estimates included second-order effects as much as possible to help ensure the completeness of the estimate. The methodology used for estimating cost differences from an established baseline was developed in a previous cost-reduction trade study.³

The reactor power was established as 125 MW (f) compared with the ANS baseline value of 330 MW(f). The core design was essentially the same as the three-element core recently adopted

for ANS. A minimum core life of 17 days and refueling time of 4 days were retained. Availability and predictability goals of the ANS were also retained.

Stringent core and safety parameter requirements were established to enhance licensability:

- The temperature of the fuel plate surfaces will be less than the saturation temperature of the cooling water ($T_{\text{wall}} < T_{\text{sat}}$) for all anticipated occurrences (i.e., occurrence frequency greater than or equal to 10^{-2} events per year).
- The critical heat flux condition is not exceeded, even assuming that normal heat transfer is lost on one side of a fuel plate, thereby forcing reliance upon single-sided fuel plate cooling. The goal here is no propagation of damage from plate to plate in the unlikely event of hot spot fuel damage.
- Aluminum structural components are kept below 100°C .

A 2-year compression of the ANS project schedule is desired, which would be feasible since less construction of buildings is required. A guest facility to be supplied by the state of Tennessee will house many of the users. This cost of this facility, estimated at \$6 million, was not included in the cost estimate. Finally, it was assumed that the soil conditions, seismic conditions, and building foundation specifications are the same as for ANS.

2.3 APPROACH

The ANS staff was assembled and the goals, objectives, and constraints for the workshop were presented. Based upon this initial information, requirements for the HFIR-CNR were determined. Specific reference was made to the differences between this new facility and the ANS in generating requirements and engineering specifications.

To carry out the assignment, personnel responsible for each work breakdown structure (WBS) level-three element of the project documented design, cost, schedule, and project risk information consistent with the study objectives and new facility requirements. This material was compiled into the design report which, along with backup information, was transmitted as record material for traceability of the workshop study.⁴ This transmitted design material formed the basis for the remainder of this report.

The first task was to determine the extent to which existing HFIR facilities could be used. A site plan for the facility was generated using the ANS principles of user-friendly research facilities and separation of research from operation and support facilities.

3. THE HFIR-CNR FACILITY

This section presents a summary of the site plan, facility design, cost, and schedule for the HFIR-CNR. Section 3.1 presents the overall site plan and indicates how HFIR facilities are expected to be used. Section 3.2 discusses the major design features of HFIR-CNR. In many instances, material in this section is presented in itemized form for clarity and ease of traceability. For those desiring more design details, a comparison of the HFIR-CNR facility with the ANS facility is presented in Appendix A and additional engineering and design details are in ref. 4.

Summary cost and schedule information is presented in the remainder of this section. More detailed cost and schedule information is presented in Appendix B and Appendix C, respectively. Scientific instruments included in HFIR-CNR are listed in Appendix D. Major contributors to the workshop are listed in Appendix E.

3.1 GENERAL SITE AND BUILDINGS

The HFIR-CNR would be located next to (west of) the present HFIR and Radiochemical Engineering Development Center (REDC) complex so that maximum use may be made of existing facilities and infrastructure. The site and building arrangements remain user-friendly and include features similar to features in the ANS design. A layout for the site is shown in Fig. 1. This layout allows for growth of HFIR-CNR and replacement of HFIR facilities in a logical and organized manner. The HFIR-CNR complex includes the following buildings and features:

- A 30-m-diameter reactor containment building that houses the HFIR-CNR reactor, the primary cooling system, the fuel handling and wet storage systems, and the cold source system. One year of spent fuel storage will be retained inside containment. Consistent with the ANS, a dry fuel storage facility with nominal 40-year capacity is not included, but space is available for it. Lower cost options for spent fuel storage may be considered.
- A guide hall housing the cold neutron guides and instruments. (See Fig. 2 for a layout of one guide hall and Appendix D for a list of instruments. Note that Fig. 1 shows the full complement of guide halls, and Fig. 2 shows only those included in the initial HFIR-CNR cost estimate.).
- A thermal guide hall housing thermal neutron scattering instruments. (See Fig. 2 for a layout of one guide hall and Appendix D for a list of instruments. Note that Fig. 1 shows the full complement of guide halls, and Fig. 2 shows only those included in the initial HFIR-CNR cost estimate.).
- A research support facility housing laboratories and shops needed to support research operations.
- A reactor support building housing equipment needed to operate the reactor and the refrigeration system needed to operate the cold source.
- An interface building used for access control, health physics monitoring and control, and security control.




Fig. 1. A layout for the High Flux Isotope Reactor-Center for Neutron Research site.




Fig. 2. A layout of the guide hall of the High Flux Isotope Reactor-Center for Neutron Research.

- Process and service buildings that house the heavy water upgrade and detritiation process equipment.
- Cooling towers, electrical substations, and other structures not available in the existing HFIR and REDC complex.
- Existing buildings in the HFIR and REDC complex are used to house the operations, maintenance, technical, quality, security, and health physics staff.
- Existing buildings in the HFIR and REDC complex provide the shops and warehouses needed to support HFIR-CNR operations and to house the HFIR-CNR mockup and other training facilities.

In developing this site plan, it was concluded that Buildings 7920, 7930, and adjoining structures, as well as the new office building under construction to the north of buildings 7914 and 7915, are not part of the HFIR complex and therefore cannot be used for HFIR-CNR. All research facilities are constructed northwest of the existing HFIR facility in what is now the parking lot area of HFIR outside the fence. The two guide halls and adjoining research support building will be included within the research zone. A small interface building of approximately 5400 ft² will include essential security and health physics monitoring and a general reception area. It was assumed that an adjoining \$6 million facility will be funded by the state of Tennessee (and therefore not included in the design and cost summary), as was the case for ANS. This structure, a guest/user facility, will be a combination of office/dormitory wing, library and computers, lounge, break room, and user liaison/handling offices.

The HFIR-CNR is divided into two distinct security zones, as was the case for ANS. Unlike in ANS plans, only a portion of the dividing fence will be a perimeter intrusion detection and assessment system (PIDAS) because the areas enclosed by the PIDAS will be limited to the reactor building, reactor support building, and primary and secondary substations.

The present HFIR access road will be a utility service road. A new road for general access will be constructed west of the Molten Salt Reactor Experiment Building, over an existing service road. Some radiation clean-up work will be required, and underground piping will have to be displaced.

The new employee/guest parking lots will accommodate 205 new spaces for HFIR-CNR and 80 for analytical chemistry personnel. The initial estimate of personnel needed for HFIR-CNR is 320, based on personnel estimates of 559 for ANS and a present HFIR staff of 189.

3.2 SUMMARY SYSTEM DESCRIPTIONS

3.2.1 Reactor, Reactor Cooling System, and Containment

The HFIR-CNR neutron source is based on a 125 MW (f), heavy-water-cooled and -moderated, compact core reactor with the following features:

- A three-element core using low-or-medium-enriched uranium fuel, in the chemical form of U₃Si₂, within an aluminum matrix. The fuel is in the form of thin, curved plates that span between two concentric sideplates. Nominal values for core parameters include a fuel plate thickness of 1.27 mm, aluminum clad thickness of 0.254 mm, coolant channel gap of 1.27 mm,

heated length of 418 mm, coolant velocity of 15 m/s, inlet pressure of 2.335 MPa, outlet pressure of 1.8 MPa, and maximum core inlet temperature of 45°C.

- A large heavy water reflector vessel that transports thermal neutrons to beam and irradiation facilities.
- A liquid deuterium cold source that slows the thermal neutrons down to low energies for transport in a cold neutron guide system to a guide hall located outside the reactor containment. Provisions are made in the design for adding a second cold source after the HFIR-CNR is constructed.
- Five containment penetrations for thermal guide systems that transport thermal neutrons to instruments in an experiment hall located outside the reactor containment.
- A reactor design that meets all Nuclear Regulatory Commission requirements for a licensed facility, in accordance with reactor safety requirements established by DOE.
- A reactor protection system that is redundant, diverse, and fully responsive to all challenges, including single-failure criteria and anticipated transients without scram of the primary shutdown system.
- Systems to refuel and maintain the reactor while maintaining barriers between light and heavy water.
- A cooling system that incorporates passive and inherent safety features. These include coolant upflow through the core, decay heat transport by natural circulation, passive accumulators for inventory control and to maintain pressure during postulated transients, and no reliance on electrical power for decay heat removal.
- A double-walled reactor containment structure with a filtered annulus. The design of the containment system is integrated with emergency planning activities so that realistic evacuation times are provided for occupants of the Oak Ridge Reservation, including ORNL, and no "immediate notification" of off-site residents is required after a postulated severe accident.

3.2.2 Beam, Instrument, Irradiation, and User Support Facilities

A layout of the guide hall is shown in Fig. 2. The HFIR-CNR complex provides the following research facilities:

- One cold source, seven cold guides with two or more split guides, five thermal guides, one remotely-operated thermal beam, and one slant beam tube. A second cold source and associated guides can be added later.
- Seven thermal and eleven cold neutron scattering instruments.
- A precision gamma-ray bolometer for nuclear physics. There is the potential to add a beam station and a radioactive ion beam facility in the future.

- Thirty target positions and a hydraulic rabbit tube for producing transuranic isotopes, especially ^{252}Cf .
- Five instrumented and five noninstrumented materials irradiation targets in a hard spectrum, with the necessary hot cell facilities to support their operation.
- Three hydraulic rabbit tube facilities for producing key medical and industrial isotopes, along with the necessary hot cell facilities to support their operation.
- Prompt gamma analysis and neutron depth profiling facilities on cold guides and four pneumatic rabbit tubes for activation analysis. Counting rooms, laboratories, and sample storage facilities needed to support the activation analysis facilities are also provided.
- A positron source and beam system based on irradiation of copper targets using a dedicated hydraulic rabbit tube.
- Facilities for instrument setup and maintenance, sample preparation, and data collection.
- User support facilities, including offices and temporary lodging, to be provided in a separate building to be constructed by the state of Tennessee.

3.2.3 Plant Systems

HFIR-CNR plant systems include the following:

- reliable electrical power systems;
- heating, ventilation and air conditioning systems that maintain habitability and that control tritium and other types of contamination;
- plant water, services, fire protection and waste systems, including the cryogenic helium refrigerator necessary for the operation of the cold source;
- a heavy water processing plant that removes tritium produced in the reactor heavy water and cold source deuterium and that removes light water contamination from all heavy water supplies;
- advanced control, data and communications systems, including a digital control room, a comprehensive data network, and a complete electronic technical and business data system.

3.3 COST ESTIMATE

Costs were developed using well-documented ANS cost estimates. Risks unique to HFIR-CNR that could increase its costs are documented in ref. 4. If these unique risks are avoided, then the accuracy of the HFIR-CNR cost estimate is similar to the accuracy of the ANS estimate. Remaining uncertainties in HFIR-CNR costs and in risks associated with its design, licensing, and construction have been adequately investigated and documented during the ANS conceptual

design. Thus, the contingency percentages used for the HFIR-CNR were similar to those for ANS. Total project costs are summarized in Tables 1 and 2. Annual operating costs are summarized in Table 3.

3.4 SCHEDULE FOR CONSTRUCTION

The project schedule is success oriented, as was that of the ANS conceptual design. The most challenging schedule item is obtaining review and approval from DOE (or other regulating bodies) of environmental, safety, and licensing documentation in a timely manner. While we recognize that this may be difficult, we believe that if the project, DOE and the licensing body work as a team, the HFIR-CNR can be constructed on the schedule shown.

The following are key schedule dates:

| | |
|--|----------------|
| Project authorization/begin Title I | October 1995 |
| Industry team in place | October 1995 |
| National Environmental Policy Act | |
| Record of decision issued | August 1997 |
| Issue preliminary safety analysis report | October 1997 |
| Begin early Title II design | December 1996 |
| Start non-nuclear construction | December 1997 |
| First nuclear concrete | November 1998 |
| Complete Title II | December 1999 |
| Issue final safety analysis report | January 2001 |
| Initial core load | February 2002 |
| Initial criticality | May 2002 |
| Project complete | September 2002 |

3.5 METHOD OF ACCOMPLISHMENT

Both programmatic direction and funding from DOE will be provided by the Office of Energy Research, as is the case for their other large scientific facility projects (e.g., the Advanced Photon Source, the Relativistic Heavy Ion Collider). The project will be managed by Lockheed Martin Energy Systems. Industrial participation (architect engineer, reactor manufacturer, and construction manager) will be obtained and managed directly by Lockheed Martin Energy Systems.

Table 1. Total project cost for the High Flux Isotope Reactor-Center for Neutron Research (all types of funding included)

| WBS element | FY 1992 dollars (\$K) | As-spent dollars (\$K) |
|--|--------------------------|---------------------------|
| 1.1 Research and development | 138,870 | 171,866 |
| 1.2 Project support | 179,426 | 231,493 |
| 1.3 Reactor systems | 114,226 | 144,768 |
| 1.4 Experiment systems | 154,938 | 200,588 |
| 1.5 Site and buildings | 188,590 | 239,015 |
| 1.6 Plant systems | 321,082 | 415,277 |
| 1.7 Operations | 128,660 | 178,727 |
| 1.8 DOE support | 5,478 | 7,087 |
| Total HFIR-CNR project cost ^a | 1,231,270 | 1,588,821 |

^a This figure does not include costs for the heavy water upgrade and detritiation facility (listed in Table 2).

Table 2. Total project cost for the High Flux Isotope Reactor-Center for Neutron Research heavy water upgrade and detritiation facility (all types of funding included)

| WBS element | FY 1992 dollars (\$K) | As-spent dollars (\$K) |
|--|--------------------------|---------------------------|
| Detritiation buildings | 7,165 | 9,081 |
| Detritiation process | 55,701 | 72,110 |
| Total D ₂ O upgrade and detritiation project cost | 62,866 | 81,191 |

Table 3. Annual operating costs for the High Flux Isotope Reactor-Center for Nuclear Research (HFIR-CNR) and for the heavy water upgrade and detritiation facility (thousands of FY 1995 dollars).

| | 35% enrichment | 20% enrichment |
|--|----------------|----------------|
| HFIR-CNR reactor and plant operating cost | 47,796 | 54,056 |
| HFIR-CNR research staff cost | 13,556 | 13,556 |
| Total HFIR-CNR operations and research costs | 61,352 | 67,612 |
| Detritiation facility operating cost | 1,671 | 1,739 |

4. REFERENCES

1. F. J. Peretz and R. S. Booth, "Advanced Neutron Source—U.S. Plans 330 MW Research Reactor Centre for 21st Century," *Nuclear Engineering International*, 39 (485) 30–33, December 1994.
2. J. Peretz, et al., *Advanced Neutron Source Conceptual Design Summary*, ORNL/TM-12184, Martin Marietta Energy Systems, Inc., Oak Ridge National Laboratory, September 1992.
3. R. S. Booth, compiler, *ANS Project Workshop on Cost Reduction*, ORNL/ANS/INT-39, Martin Marietta Energy Systems, Inc., Oak Ridge National Laboratory, October 1992.
4. F. J. Peretz, , *Design Material from the Feasibility Workshop for a High Flux Isotope Reactor-Center for Neutron Research Facility*, ANS-1201-95-5, March 1995. This document was transmitted to the ANS records system via transmittal 95-054.

APPENDIXES

Appendix A

COMPARISON OF THE HFIR-CNR AND ANS FACILITIES

A.1 COMPARISON OF CAPABILITIES

1. The neutron flux distribution of the HFIR-CNR reactor is generally similar to that of the ANS reactor, but it is lower by the ratio of the fission power of the two designs. The power of the HFIR-CNR reactor, and therefore the flux available at most beam stations and irradiation facilities, is about 40% that of the corresponding ANS facility. In many cases, the research capability of the facility is directly proportional to the flux. In some cases, the lower flux may preclude certain types of experiments. The performance of some irradiation facilities (especially the transuranium production facilities) is proportional to the flux raised to some power above one, and thus the performance is reduced further than the simple ratio of flux.
2. The following neutron scattering instruments in the ANS complement, and their associated costs, have not been included in HFIR-CNR. The method of funding in the ANS Project cost estimate is also indicated. Instruments to be procured with line item funds were to be designed and installed as part of the ANS Project, whereas those procured with operating funds were in many cases to be designed and installed by other research organizations.

| | | |
|------|--|-----------|
| L-5 | High resolution powder diffractometer | Operating |
| T-6 | Diffuse scattering time-of-flight spectrometer | Line item |
| T-7 | Diffuse scattering time-of-flight spectrometer | Operating |
| T-8 | Time-of-flight spectrometer | Line item |
| D-1 | Multichopper time-of-flight spectrometer | Line item |
| L-6 | Time-focusing time-of-flight spectrometer | Operating |
| H-4 | Triple-axis spectrometer | Line item |
| D-11 | Triple-axis spectrometer | Operating |
| L-9 | Triple-axis spectrometer | Operating |
| L-11 | Double crystal small angle neutron scattering (SANS) | Operating |
| D-5 | SANS 40m | Operating |
| L-2 | SANS 20m | Operating |
| D-6 | SANS 20m | Operating |
| H-2 | General purpose liquids diffractometer | Line item |
| D-10 | Backscattering spectrometer | Operating |
| V-1 | Very cold neutron optical bench | Operating |
| U-1 | Ultracold neutron turbine | Line item |
| C-1 | Slant cold neutron station | Operating |

3. The following nuclear and fundamental physics instruments in the ANS complement have not been included (the method of funding in the ANS Project is also indicated).

| | | |
|------|---|-----------|
| T-9 | Through-tube loading station | Line item |
| T-10 | Ultrahigh resolution gamma spectroscopy | Line item |

| | | |
|------|----------------------------|-----------|
| D-8 | Weak interaction physics | Operating |
| L-12 | Parity violation | Line item |
| D-14 | Nuclear structure | Operating |
| D-15 | Nuclear spectroscopy | Operating |
| T-13 | Isotope separation on-line | Line item |

4. The two slant materials irradiation facilities included in the ANS design have been deleted.
5. The four vertical isotope production facilities included in the ANS design have been deleted.
6. Three of the seven pneumatic rabbit tubes provided for activation analysis in the ANS design have been deleted. The support facilities for activation analysis have been reduced by a corresponding amount.
7. Laboratories and shops that support research operations have been reduced in proportion to the number of instruments.

A.2 COMPARISON OF COST

The design and estimate for HFIR-CNR was generated using the exceptionally detailed (and independently verified) conceptual design and cost information developed for ANS. In using the ANS design information to generate the design and estimate for HFIR-CNR, the following changes were made to the ANS data:

A.2.2 Reactor, Reactor Cooling, and Containment Systems

1. The reflector vessel design is simplified with respect to the ANS design by the reduction in the number of beam and irradiation facility penetrations. This effect is offset by complications resulting from combining the primary and reflector cooling systems.
2. Because of the lower flux and heating rates in the HFIR-CNR reactor, a zirconium alloy is used for the core pressure boundary tube and possibly the beam tubes. Although this may increase the direct cost of the reactor components, it increases reactivity and core life and decreases the operating cost.
3. Because the reactor power is reduced considerably, many accident scenarios are less challenging for the HFIR-CNR reactor. Thus the required control rod response speed is less than in the ANS design, and the reactor control system costs are somewhat lower.
4. One primary and one secondary cooling system loop have been deleted. These loops were used as an on-line spare in the ANS design.
5. Cooling of the HFIR-CNR reflector is accomplished using the primary cooling loops. Thus the separate reflector cooling loops provided in the ANS design are deleted.

6. Plate heat exchangers are used instead of shell and tube designs to reduce the cost and size of the primary cooling loops in this lower pressure system.
7. Pony motors and separate emergency heat exchangers are not needed for the HFIR-CNR cooling systems.
8. All primary and secondary cooling system components are reduced in size and cost using appropriate power scaling factors.
9. The basic design of the reactor containment system remains the same. However, because of the lower power level of the HFIR-CNR, the containment structure is half the diameter of and somewhat lower in height than the ANS design. This reduces the size and cost of the containment ventilation and filtration systems. The containment is not normally occupied during operation; the size, number, and cost of airlocks has been reduced. The number of other penetrations in the containment has also been reduced. The reduced reactor power level [125 vs 330 MW (t)] allows reduction of the containment volume without an increase in the primary containment wall thickness. Thus the HFIR-CNR preserves the containment capability of the ANS conceptual design.

A.2.2 Research Facilities and User Support

1. One cold source and its associated cold neutron guides were deleted; but provision is made for adding them later, after operations have begun and the first guide hall is saturated.
2. Twenty-five beam instruments were deleted, as described under research capabilities.
3. Two slant materials irradiation facilities, four vertical isotope facilities, and three pneumatic tubes were deleted, as described under research capabilities.
4. Laboratories and shops needed to support research operations were scaled with the number of instruments. A research support structure encircles the thermal instrument room outside containment. User support is provided in a building that it is assumed will be built by the state of Tennessee.

A.2.3 Site, Buildings, and Plant Systems

1. The reactor containment building will have a diameter half that of the corresponding ANS building.
2. The reactor support building will be half the size of the corresponding ANS building.
3. The guide hall will be 60% of the size of the ANS guide hall. Provision will be made for the construction of a second guide hall at a later time.
4. The office building has been eliminated; many of its functions will be provided by a guest facility expected to be constructed by the state of Tennessee, and the rest will be provided by an interface building (see next item).

5. A new interface building has been added. This new 5400 ft² building replaces some of the functions of the ANS office building.
6. Operations support has been eliminated (existing HFIR facilities are to be used instead)
7. The mockup building has been eliminated (existing HFIR facilities are to be used instead)
8. The research support building will be 62% the size of the corresponding ANS building.
9. The detritiation buildings will be 80% of the size of the corresponding ANS buildings. The detritiation buildings are costed separately, so that the decision to construct the detritiation facility can be made separately from the decision to build HFIR-CNR.
10. The positron facility will be 34% of the size of the corresponding ANS building.
11. Most plant systems that support reactor operations are reduced in cost using an appropriate power scaling factor (See ref. 4).
12. The two independent 161-kV lines supplying the site with electrical power in the ANS design have been deleted. A second 13.8-kV line is brought to the HFIR site to improve the reliability of the existing HFIR power supply.
13. Emergency power loads have been greatly reduced, so Class 1E standby diesel generators are deleted; Class-1E battery systems will power the remaining emergency loads. Commercial grade standby generator sets have been added to supply non-Class 1E power during loss of off-site power. Emergency cooling of the main control room is provided by a passive design similar to that used in the ANS.
14. A processing plant is provided to remove tritium and light water contamination from the HFIR-CNR heavy water inventory. This plant will have other uses in the DOE complex as well. The detritiation process is costed separately so that the decision to construct the detritiation facility can be made separately from the decision to build HFIR-CNR.
15. The scope and thus cost of the plant control simulator has been reduced.
16. Since each fuel element cannot become supercritical as a result of any upset during refueling, the instrument and control equipment for refueling will not be Class 1E.

A.2.4 Project Cost

1. Research and development costs are reduced because of a substantial increase in thermal margins, the elimination of the hot source, the elimination of the need for neutron poisons in the refueling process, and numerous other simplifications in the reactor design.
2. Other project support cost elements (e.g., administration, quality assurance) have been reduced as appropriate to correspond to the 2-year reduction in the project schedule.

A.2.5 Summary Cost Estimates

Costs for HFIR-CNR were generally estimated by reviewing the ANS cost estimate data and changing costs to reflect the specific differences between ANS and HFIR-CNR. The key assumptions and methodology used are described in Ref. 4. The spreadsheet format developed to display the ANS costs over time were then used to summarize costs for HFIR-CNR. A summary of the escalated costs for ANS and HFIR-CNR, and the difference between them, is included in Tables A.1 and A.2.

A.3 COMPARISON OF SCHEDULE

The schedule for HFIR-CNR is 2 years shorter than for the much larger ANS Project. A key element of this shortened schedule is the assumption that the DOE office responsible for certification of HFIR-CNR will provide a staff co-located with the design team starting October 1, 1995, to ensure early and ongoing interaction and continual review of the design and safety program. It is also assumed that the certifying DOE office will take no more than one whole year to review the preliminary safety analysis report and one whole year to review the final safety analysis report.

Key schedule dates in the ANS and HFIR-CNR schedules compare as follows.

| | <u>ANS schedule</u> | <u>HFIR-CNR schedule</u> |
|--|---------------------|--------------------------|
| Project authorization/begin Title I | October 1995 | October 1995 |
| Industry team in place | October 1995 | October 1995 |
| Issue NEA record of decision | November 1996 | August 1997 |
| Issue preliminary safety analysis report | October 1997 | October 1997 |
| Begin early Title II design | October 1997 | December 1996 |
| Start non-nuclear construction | December 1997 | December 1997 |
| First nuclear concrete | November 1998 | November 1998 |
| Complete Title II | October 2001 | December 1999 |
| Issue final safety analysis report | January 2003 | January 2001 |
| Initial core load | March 2004 | February 2002 |
| Initial criticality | April 2004 | May 2002 |
| Project complete | September 2004 | September 2002 |

Table A.1. Comparison of total costs for the Advanced Neutron Source and HFIR-CNR* projects (all types of funding included; escalated to year spent)

| WBS element | ANS cost (\$K) | HFIR-CNR (\$K) | Cost reduction (\$K) |
|----------------------------|------------------------|------------------------|----------------------|
| 1.1 Research & development | 211,113 | 171,866 | 39,247 |
| 1.2 Project support | 342,036 | 231,493 | 110,543 |
| 1.3 Reactor systems | 178,497 | 144,768 | 33,729 |
| 1.4 Experiment systems | 343,480 | 200,588 | 142,892 |
| 1.5 Site and buildings | 502,695 | 239,015 | 263,680 |
| 1.6 Plant systems | 792, 412 | 415,277 | 377,135 |
| 1.7 Operations | 321,537 | 178,727 | 142,810 |
| 1.8 DOE support | 9,120 | 7,087 | 2,033 |
| Total project cost | 2,700,890 ^b | 1,588,821 ^c | 1,122,069 |

* High Flux Isotope Reactor-Center for Neutron Research

^b Does not include costs of the heavy water upgrade and detritiation facility or funds previously spent on the Advanced Neutron Source research and development and design. When heavy water upgrade and detritiation costs (\$123 million) and prior year costs (\$102 million) are added to the ANS Project cost, the total ANS cost comes to \$2,925 million.

^c Does not include heavy water upgrade and detritiation costs (listed in Table A.2).

Table A.2. Comparison of total costs for the ANS and HFIR-CNR heavy water upgrade and detritiation facilities (all types of funding included; escalated to year spent)

| WBS element | ANS cost (\$K) | HFIR-CNR (\$K) | Cost reduction (\$K) |
|------------------------|----------------|----------------|----------------------|
| Detritiation buildings | 9,504 | 9,081 | 423 |
| Detritiation process | 113,191 | 72,110 | 41,081 |
| Total project cost | 122,695 | 81,191 | 41,504 |

Appendix B

HFIR-CNR COSTS BY WBS AND FUNDING TYPE

To simplify the task of developing a cost estimate for an upgraded HFIR, the present ANS WBS was used as a starting point. The ANS cost estimate baseline that is the basis for the FY 1996 Congressional data sheet (FY 1995 line-item start) was used as a starting point for evaluating and establishing cost estimates for activities, components, systems, subsystems, and/or structures. The estimating activities used FY 1992 constant year dollars, which are the basis for the ANS CDR and all other cost estimates since that time. After an estimate was established in fixed dollars, the estimate was spread in time based on the HFIR-CNR schedule for the activity using standard bell distributions or "S" curves, and then escalated from FY 1992 to actual year dollars.

The cost estimate for the HFIR-CNR was developed at WBS Level 3 and rolled up to establish the total estimated construction cost and total project cost. This established the line item construction budget, the operation expense budget for research and development and operations support, and the capital equipment budget that supports the research and development and operations activities.

The estimates were established by evaluating assumptions, scaling down or eliminating elements of the estimated cost, and comparing ANS function and HFIR-CNR function for all systems. Costs were developed through

- Eliminating an item, system or function entirely.
- Scaling down in area or size, which would then scale down the cost in a somewhat linear fashion.
- Scaling down as a function of the power: $(P_2/P_1)^{0.6}$
where

P_1 is the ANS power, 330 MW, and
 P_2 is the HFIR-CNR power, 125 MW.

(See ref. 3 for more information on this expression.)

- Reducing level-of-effort activities by the ratio of the duration of the ANS schedule for the activity to the duration of the HFIR-CNR schedule for the activity

Four tables are presented in this appendix (total project costs, pages B-3 to B-5; line item or capital costs, pages B-6 to B-8; operating expenses, pages B-9 to B-11; and capital equipment, pages B-12 to B-14). Costs are arranged by level 3 WBS numbers.

| Total Project Cost | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|---------------------|-----------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|---------|
| April 1994 Baseline | | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.1.1 | Reactor Core Development | 22,604 | 18,267 | 2,686 | 3,997 | 4,029 | 4,598 | 3,846 | 2,438 | 1,389 | 22,983 |
| 1.1.2 | Fuel Development | 18,077 | 15,923 | 2,162 | 4,916 | 6,004 | 4,538 | 693 | 657 | 597 | 19,567 |
| 1.1.3 | Corrosion Tests & Analysis | 2,415 | 1,193 | 669 | 585 | 135 | 0 | 0 | 0 | 0 | 1,389 |
| 1.1.4 | Core Flow Tests | 39,388 | 21,675 | 1,924 | 5,108 | 9,423 | 6,641 | 3,696 | 0 | 0 | 26,792 |
| 1.1.5 | Control Concepts | 673 | 716 | 126 | 158 | 164 | 95 | 98 | 102 | 164 | 908 |
| 1.1.6 | Critical Experiments | 6,741 | 8,249 | 311 | 2,667 | 2,390 | 3,024 | 1,864 | 0 | 0 | 10,255 |
| 1.1.7 | Matrls Data, Tests and Anly | 20,519 | 21,614 | 5,120 | 8,754 | 5,341 | 4,441 | 1,718 | 670 | 136 | 26,180 |
| 1.1.8 | Cold Source Development | 8,970 | 9,324 | 1,310 | 2,411 | 2,012 | 1,947 | 1,297 | 1,242 | 1,556 | 11,774 |
| 1.1.9 | Beam Tube, Guide, Inst Dev | 16,472 | 15,389 | 1,030 | 2,099 | 3,903 | 5,282 | 3,860 | 1,766 | 1,716 | 19,656 |
| 1.1.10 | Hot Source Development | 8,438 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.11 | Neutron Tranport & Shldng | 6,138 | 5,419 | 1,250 | 1,399 | 1,438 | 1,477 | 1,074 | 0 | 0 | 6,637 |
| 1.1.12 | I&C System Development | 4,022 | 2,750 | 700 | 953 | 628 | 526 | 214 | 222 | 117 | 3,360 |
| 1.1.13 | Facility Concepts | 20,612 | 18,351 | 4,638 | 5,742 | 5,064 | 3,718 | 2,137 | 863 | 201 | 22,364 |
| 1.1 | Research & Development | 175,068 | 138,870 | 21,926 | 38,790 | 40,532 | 36,287 | 20,496 | 7,959 | 5,876 | 171,866 |
| 1.2.1 | Proj Mgmt & Adminstn | 147,881 | 79,841 | 3,016 | 9,055 | 16,469 | 24,876 | 26,969 | 18,278 | 4,342 | 103,005 |
| 1.2.2 | Systems Engineering | 21,747 | 11,720 | 307 | 1,163 | 2,373 | 3,714 | 4,107 | 2,840 | 669 | 15,173 |
| 1.2.3 | Safety | 58,578 | 58,578 | 1,533 | 5,812 | 11,862 | 18,561 | 20,529 | 14,192 | 3,345 | 75,834 |
| 1.2.4 | Envrt & Waste Mgmt | 5,991 | 3,349 | 1,297 | 1,040 | 454 | 627 | 496 | 130 | 0 | 4,044 |
| 1.2.5 | Quality Assurance | 27,089 | 20,393 | 526 | 2,002 | 4,104 | 6,452 | 7,168 | 4,978 | 1,179 | 26,409 |
| 1.2.6 | Training | 3,999 | 2,155 | 81 | 306 | 624 | 862 | 681 | 178 | 0 | 2,732 |
| 1.2.7 | Test & Evaluation | 6,288 | 3,389 | 127 | 480 | 982 | 1,355 | 1,071 | 280 | 0 | 4,295 |
| 1.2 | Project Support | 271,575 | 179,426 | 6,887 | 19,859 | 36,870 | 56,446 | 61,021 | 40,875 | 9,534 | 231,493 |
| 1.3.1 | Reactor Assembly | 27,295 | 27,295 | 1,025 | 3,869 | 7,906 | 10,915 | 8,624 | 2,254 | 0 | 34,594 |
| 1.3.2 | Refueling | 45,218 | 28,791 | 1,081 | 4,081 | 8,339 | 11,513 | 9,096 | 2,378 | 0 | 36,489 |
| 1.3.3 | Reactor I&C | 33,706 | 23,653 | 888 | 3,353 | 6,851 | 9,459 | 7,473 | 1,954 | 0 | 29,977 |
| 1.3.4 | Fuel | 2,984 | 4,038 | 152 | 572 | 1,170 | 1,615 | 1,276 | 334 | 0 | 5,118 |
| 1.3.5 | Reactor Mockup | 22,723 | 22,723 | 853 | 3,221 | 6,582 | 9,087 | 7,179 | 1,877 | 0 | 28,799 |
| 1.3.6 | Maintenance | 7,726 | 7,726 | 290 | 1,095 | 2,238 | 3,090 | 2,441 | 638 | 0 | 9,791 |
| 1.3 | Reactor Systems | 139,653 | 114,226 | 4,290 | 16,191 | 33,085 | 45,679 | 36,088 | 9,434 | 0 | 144,768 |

| Total Project Cost | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|---------------------|---------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|---------|
| April 1994 Baseline | | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.4.1 | Neutron Transport | 55,908 | 39,839 | 1,043 | 3,953 | 8,068 | 12,623 | 13,962 | 9,652 | 2,275 | 51,575 |
| 1.4.2 | Neutron Scat Inst | 84,402 | 40,352 | 1,056 | 4,004 | 8,172 | 12,786 | 14,141 | 9,776 | 2,304 | 52,239 |
| 1.4.3 | Nuc & Fund Physics | 15,034 | 3,413 | 89 | 339 | 691 | 1,081 | 1,196 | 827 | 195 | 4,418 |
| 1.4.4 | Trans U Production | 21,150 | 21,012 | 550 | 2,085 | 4,255 | 6,658 | 7,364 | 5,091 | 1,200 | 27,202 |
| 1.4.5 | Materials Irrad. Facility | 9,773 | 8,232 | 215 | 817 | 1,667 | 2,608 | 2,885 | 1,994 | 470 | 10,657 |
| 1.4.6 | Isotope Prodn Facility | 6,634 | 3,951 | 103 | 392 | 800 | 1,252 | 1,385 | 957 | 226 | 5,115 |
| 1.4.7 | Analytical Chem Fac | 36,402 | 18,791 | 483 | 1,844 | 3,786 | 5,949 | 6,608 | 4,582 | 1,083 | 24,334 |
| 1.4.8 | Instrument Supprt Fac | 9,428 | 5,479 | 143 | 544 | 1,110 | 1,736 | 1,920 | 1,327 | 313 | 7,093 |
| 1.4.9 | Comptr & Data Hndlg | 4,492 | 2,059 | 54 | 204 | 417 | 652 | 722 | 499 | 118 | 2,666 |
| 1.4.10 | Cold Source | 17,966 | 11,810 | 309 | 1,172 | 2,392 | 3,742 | 4,139 | 2,861 | 674 | 15,289 |
| 1.4.11 | Hot Source | 1,856 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.4 | Experiment Systems | 263,045 | 154,938 | 4,046 | 15,353 | 31,357 | 49,087 | 54,320 | 37,567 | 8,857 | 200,588 |
| 1.5.1 | Land Improvements | 41,584 | 20,838 | 783 | 2,954 | 6,036 | 8,333 | 6,583 | 1,721 | 0 | 26,410 |
| 1.5.2 | Reactor Building | 136,569 | 52,554 | 1,974 | 7,449 | 15,222 | 21,016 | 16,604 | 4,341 | 0 | 66,606 |
| 1.5.3 | React/Opns Suppt | 79,161 | 52,554 | 1,974 | 7,449 | 15,222 | 21,016 | 16,604 | 4,341 | 0 | 66,606 |
| 1.5.4 | GHall/Res Suppt | 42,871 | 30,754 | 1,155 | 4,359 | 8,908 | 12,298 | 9,716 | 2,540 | 0 | 38,977 |
| 1.5.5 | Office/Interface Bldg | 32,529 | 1,090 | 41 | 155 | 316 | 436 | 344 | 90 | 0 | 1,381 |
| 1.5.6 | Detritiation Building | 7,704 | 7,165 | 269 | 1,016 | 2,075 | 2,865 | 2,264 | 592 | 0 | 9,081 |
| 1.5.7 | Other Structures | 32,581 | 8,837 | 332 | 1,253 | 2,560 | 3,534 | 2,792 | 730 | 0 | 11,200 |
| 1.5.8 | Construction Support | 21,963 | 21,963 | 825 | 3,113 | 6,362 | 8,783 | 6,939 | 1,814 | 0 | 27,836 |
| 1.5 | Site & Buildings | 394,963 | 195,755 | 7,351 | 27,748 | 56,700 | 78,282 | 61,846 | 16,168 | 0 | 248,096 |
| 1.6.0 | Plant Systems Integration | 2,858 | 1,225 | 46 | 174 | 355 | 490 | 387 | 101 | 0 | 1,553 |
| 1.6.1 | Reactor Water Systems | 115,962 | 53,370 | 1,397 | 5,296 | 10,808 | 16,910 | 18,703 | 12,930 | 3,047 | 69,092 |
| 1.6.2 | Elec & Comm Systems | 121,802 | 63,647 | 1,666 | 6,315 | 12,889 | 20,167 | 22,305 | 15,420 | 3,634 | 82,396 |
| 1.6.3 | Environmental Systems | 69,315 | 42,445 | 1,111 | 4,212 | 8,595 | 13,449 | 14,875 | 10,283 | 2,424 | 54,949 |
| 1.6.4 | Plant Water Systems | 91,437 | 44,831 | 1,173 | 4,448 | 9,079 | 14,205 | 15,711 | 10,861 | 2,560 | 58,037 |
| 1.6.5 | Plant Service Systems | 44,332 | 28,906 | 757 | 2,868 | 5,854 | 9,159 | 10,130 | 7,003 | 1,651 | 37,421 |
| 1.6.6 | Plant Fire Protection | 13,184 | 5,639 | 148 | 559 | 1,142 | 1,787 | 1,976 | 1,366 | 322 | 7,300 |
| 1.6.7 | Plant Waste Systems | 20,248 | 9,748 | 255 | 967 | 1,974 | 3,089 | 3,416 | 2,362 | 557 | 12,620 |
| 1.6.8 | Heavy Water Dtrn & Upgd | 87,385 | 55,701 | 1,458 | 5,527 | 11,280 | 17,649 | 19,520 | 13,495 | 3,181 | 72,110 |
| 1.6.9 | Plant I, C & Data Systems | 112,945 | 68,282 | 1,496 | 6,710 | 15,806 | 24,490 | 22,424 | 13,850 | 3,264 | 88,040 |
| 1.6.10 | Maintenance & GPE | 13,931 | 2,989 | 78 | 297 | 605 | 947 | 1,047 | 724 | 171 | 3,870 |
| 1.6 | Plant Systems | 693,398 | 376,783 | 9,585 | 37,373 | 78,386 | 122,341 | 130,496 | 88,397 | 20,810 | 487,387 |

| Total Project Cost | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|---------------------|---------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|-----------|
| April 1994 Baseline | | FY 1992 | FY 1992 | | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | Actual Year \$k | | | | | | | TOTAL |
| | | | | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | |
| 1.7.1 | Administrative Support | 7,514 | 3,708 | 50 | 104 | 217 | 395 | 820 | 1,701 | 1,764 | 5,052 |
| 1.7.2 | Management & Planning | 11,343 | 10,674 | 368 | 573 | 1,588 | 2,273 | 2,577 | 3,340 | 3,463 | 14,181 |
| 1.7.3 | Maintenance | 12,319 | 6,868 | 0 | 0 | 0 | 470 | 489 | 1,715 | 6,975 | 9,649 |
| 1.7.4 | Health&Safety | 9,058 | 6,163 | 278 | 288 | 374 | 623 | 1,620 | 2,521 | 2,614 | 8,317 |
| 1.7.5 | Training | 6,825 | 1,623 | 0 | 14 | 60 | 181 | 377 | 782 | 811 | 2,225 |
| 1.7.6 | QA | 9,368 | 8,680 | 109 | 278 | 771 | 1,069 | 2,830 | 3,271 | 3,392 | 11,720 |
| 1.7.7 | Utilities | 3,687 | 8,476 | 0 | 0 | 0 | 778 | 889 | 922 | 9,317 | 11,907 |
| 1.7.8 | Fuel | 30,224 | 10,233 | 0 | 0 | 0 | 0 | 3,019 | 10,956 | 0 | 13,975 |
| 1.7.9 | Replacing Equipt & Mods | 0 | 1,000 | 0 | 0 | 0 | 319 | 332 | 344 | 357 | 1,352 |
| 1.7.10 | Security | 1,585 | 1,232 | 75 | 104 | 135 | 169 | 234 | 303 | 628 | 1,647 |
| 1.7.11 | Reactor Operations | 50,159 | 26,790 | 0 | 0 | 979 | 3,133 | 7,717 | 12,195 | 12,659 | 36,683 |
| 1.7.12 | Rsrch Operations | 75,341 | 33,793 | 0 | 0 | 0 | 4,016 | 8,299 | 16,786 | 17,421 | 46,522 |
| 1.7.13 | Initial Purchases | 8,256 | 9,420 | 569 | 437 | 147 | 639 | 3,319 | 4,818 | 5,567 | 15,496 |
| 1.7 Operations | | 225,681 | 128,660 | 1,449 | 1,798 | 4,272 | 14,065 | 32,520 | 59,654 | 64,969 | 178,727 |
| 1.8.1 | DOE Support Subcontractng | 7,031 | 5,478 | 167 | 539 | 1,127 | 1,722 | 1,905 | 1,317 | 310 | 7,087 |
| 1.8 DOE Support | | 7,031 | 5,478 | 167 | 539 | 1,127 | 1,722 | 1,905 | 1,317 | 310 | 7,087 |
| TOTAL | | 2,170,415 | 1,294,136 | 55,701 | 157,651 | 282,328 | 403,911 | 398,692 | 261,373 | 110,356 | 1,670,011 |

| LINE ITEM | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|--------------|-----------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|---------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | TOTAL |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.1.1 | Reactor Core Development | 8,945 | 12,803 | 1,195 | 2,606 | 2,755 | 3,203 | 3,177 | 2,029 | 1,325 | 16,289 |
| 1.1.2 | Fuel Development | 8,419 | 7,626 | 0 | 1,432 | 3,255 | 3,427 | 478 | 496 | 514 | 9,600 |
| 1.1.3 | Corrosion Tests & Analysis | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.4 | Core Flow Tests | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.5 | Control Concepts | 364 | 337 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.6 | Critical Experiments | 0 | 0 | 0 | 0 | 0 | 95 | 98 | 102 | 164 | 459 |
| 1.1.7 | Matrls Data, Tests and Anly | 2,308 | 3,988 | 188 | 528 | 1,413 | 1,471 | 1,018 | 340 | 86 | 5,043 |
| 1.1.8 | Cold Source Development | 3,114 | 3,090 | 183 | 0 | 0 | 672 | 924 | 991 | 1,409 | 4,179 |
| 1.1.9 | Beam Tube, Guide, Inst Dev | 2,486 | 1,317 | 0 | 0 | 0 | 0 | 231 | 523 | 1,089 | 1,843 |
| 1.1.10 | Hot Source Development | 1,847 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.11 | Neutron Tranport & Shldng | 5,447 | 5,316 | 1,195 | 1,399 | 1,438 | 1,407 | 1,074 | 0 | 0 | 6,512 |
| 1.1.12 | I&C System Development | 1,302 | 944 | 56 | 148 | 252 | 206 | 214 | 222 | 117 | 1,213 |
| 1.1.13 | Facility Concepts | 8,509 | 7,300 | 372 | 2,885 | 3,002 | 2,250 | 430 | 0 | 0 | 8,939 |
| 1.1 | Research & Development | 42,740 | 42,721 | 3,189 | 8,996 | 12,115 | 12,729 | 7,644 | 4,702 | 4,704 | 54,078 |
| 1.2.1 | Proj Mgmt & Adminstn | 138,104 | 74,429 | 1,948 | 7,385 | 15,072 | 23,583 | 26,084 | 18,032 | 4,250 | 96,355 |
| 1.2.2 | Systems Engineering | 21,747 | 11,720 | 307 | 1,163 | 2,373 | 3,714 | 4,107 | 2,840 | 669 | 15,173 |
| 1.2.3 | Safety | 42,967 | 42,967 | 1,125 | 4,263 | 8,701 | 13,614 | 15,058 | 10,410 | 2,453 | 55,624 |
| 1.2.4 | Envrt & Waste Mgmt | 2,911 | 1,569 | 59 | 222 | 454 | 627 | 496 | 130 | 0 | 1,989 |
| 1.2.5 | Quality Assurance | 24,055 | 17,965 | 470 | 1,783 | 3,638 | 5,692 | 6,296 | 4,353 | 1,026 | 23,257 |
| 1.2.6 | Training | 3,999 | 2,155 | 81 | 306 | 624 | 862 | 681 | 178 | 0 | 2,732 |
| 1.2.7 | Test & Evaluation | 6,288 | 3,389 | 127 | 480 | 982 | 1,355 | 1,071 | 280 | 0 | 4,295 |
| 1.2 | Project Support | 240,072 | 154,194 | 4,117 | 15,602 | 31,845 | 49,448 | 53,792 | 36,222 | 8,398 | 199,424 |
| 1.3.1 | Reactor Assembly | 27,295 | 27,295 | 1,025 | 3,869 | 7,906 | 10,915 | 8,624 | 2,254 | 0 | 34,594 |
| 1.3.2 | Refueling | 45,218 | 28,791 | 1,081 | 4,081 | 8,339 | 11,513 | 9,096 | 2,378 | 0 | 36,489 |
| 1.3.3 | Reactor I&C | 33,706 | 23,653 | 888 | 3,353 | 6,851 | 9,459 | 7,473 | 1,954 | 0 | 29,977 |
| 1.3.4 | Fuel | 2,984 | 4,038 | 152 | 572 | 1,170 | 1,615 | 1,276 | 334 | 0 | 5,118 |
| 1.3.5 | Reactor Mockup | 22,723 | 22,723 | 853 | 3,221 | 6,582 | 9,087 | 7,179 | 1,877 | 0 | 28,799 |
| 1.3.6 | Maintenance | 7,726 | 7,726 | 290 | 1,095 | 2,238 | 3,090 | 2,441 | 638 | 0 | 9,791 |
| 1.3 | Reactor Systems | 139,653 | 114,226 | 4,290 | 16,191 | 33,085 | 45,679 | 36,088 | 9,434 | 0 | 144,768 |

| LINE ITEM | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|--------------|---------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|---------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.4.1 | Neutron Transport | 55,908 | 39,839 | 1,043 | 3,953 | 8,068 | 12,623 | 13,962 | 9,652 | 2,275 | 51,575 |
| 1.4.2 | Neutron Scat Inst | 60,441 | 40,352 | 1,056 | 4,004 | 8,172 | 12,786 | 14,141 | 9,776 | 2,304 | 52,239 |
| 1.4.3 | Nuc & Fund Physics | 11,096 | 3,413 | 89 | 339 | 691 | 1,081 | 1,196 | 827 | 195 | 4,418 |
| 1.4.4 | Trans U Production | 21,150 | 21,012 | 550 | 2,085 | 4,255 | 6,658 | 7,364 | 5,091 | 1,200 | 27,202 |
| 1.4.5 | Materials Irrad. Facility | 9,773 | 8,232 | 215 | 817 | 1,667 | 2,608 | 2,885 | 1,994 | 470 | 10,657 |
| 1.4.6 | Isotope Prodtn Facility | 6,634 | 3,951 | 103 | 392 | 800 | 1,252 | 1,385 | 957 | 226 | 5,115 |
| 1.4.7 | Analytical Chem Fac | 33,547 | 18,446 | 483 | 1,830 | 3,735 | 5,845 | 6,464 | 4,469 | 1,053 | 23,880 |
| 1.4.8 | Instrument Supprt Fac | 9,428 | 5,479 | 143 | 544 | 1,110 | 1,736 | 1,920 | 1,327 | 313 | 7,093 |
| 1.4.9 | Comptr & Data Hndlg | 4,492 | 2,059 | 54 | 204 | 417 | 652 | 722 | 499 | 118 | 2,666 |
| 1.4.10 | Cold Source | 17,966 | 11,810 | 309 | 1,172 | 2,392 | 3,742 | 4,139 | 2,861 | 674 | 15,289 |
| 1.4.11 | Hot Source | 1,856 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.4 | Experiment Systems | 232,290 | 154,593 | 4,046 | 15,339 | 31,306 | 48,983 | 54,177 | 37,454 | 8,827 | 200,133 |
| 1.5.1 | Land Improvements | 41,584 | 20,838 | 783 | 2,954 | 6,036 | 8,333 | 6,583 | 1,721 | 0 | 26,410 |
| 1.5.2 | Reactor Building | 136,569 | 52,554 | 1,974 | 7,449 | 15,222 | 21,016 | 16,604 | 4,341 | 0 | 66,606 |
| 1.5.3 | React/Opns Suppt | 79,161 | 52,554 | 1,974 | 7,449 | 15,222 | 21,016 | 16,604 | 4,341 | 0 | 66,606 |
| 1.5.4 | GHall/Res Suppt | 42,871 | 30,754 | 1,155 | 4,359 | 8,908 | 12,298 | 9,716 | 2,540 | 0 | 38,977 |
| 1.5.5 | Office/Interface Bldg | 32,529 | 1,090 | 41 | 155 | 316 | 436 | 344 | 90 | 0 | 1,381 |
| 1.5.6 | Detritiation Building | 7,704 | 7,165 | 269 | 1,016 | 2,075 | 2,865 | 2,264 | 592 | 0 | 9,081 |
| 1.5.7 | Other Structures | 32,581 | 8,837 | 332 | 1,253 | 2,560 | 3,534 | 2,792 | 730 | 0 | 11,200 |
| 1.5.8 | Construction Support | 21,963 | 21,963 | 825 | 3,113 | 6,362 | 8,783 | 6,939 | 1,814 | 0 | 27,836 |
| 1.5 | Site & Buildings | 394,963 | 195,755 | 7,351 | 27,748 | 56,700 | 78,282 | 61,846 | 16,168 | 0 | 248,096 |
| 1.6.0 | Plant Systems Integration | 2,858 | 1,225 | 46 | 174 | 355 | 490 | 387 | 101 | 0 | 1,553 |
| 1.6.1 | Reactor Water Systems | 115,962 | 53,370 | 1,397 | 5,296 | 10,808 | 16,910 | 18,703 | 12,930 | 3,047 | 69,092 |
| 1.6.2 | Elec & Comm Systems | 121,802 | 63,647 | 1,666 | 6,315 | 12,889 | 20,167 | 22,305 | 15,420 | 3,634 | 82,396 |
| 1.6.3 | Environmental Systems | 69,315 | 42,445 | 1,111 | 4,212 | 8,595 | 13,449 | 14,875 | 10,283 | 2,424 | 54,949 |
| 1.6.4 | Plant Water Systems | 91,437 | 44,831 | 1,173 | 4,448 | 9,079 | 14,205 | 15,711 | 10,861 | 2,560 | 58,037 |
| 1.6.5 | Plant Service Systems | 44,332 | 28,906 | 757 | 2,868 | 5,854 | 9,159 | 10,130 | 7,003 | 1,651 | 37,421 |
| 1.6.6 | Plant Fire Protection | 13,184 | 5,639 | 148 | 559 | 1,142 | 1,787 | 1,976 | 1,366 | 322 | 7,300 |
| 1.6.7 | Plant Waste Systems | 20,248 | 9,748 | 255 | 967 | 1,974 | 3,089 | 3,416 | 2,362 | 557 | 12,620 |
| 1.6.8 | Heavy Water Dtrn & Upgd | 87,385 | 55,701 | 1,458 | 5,527 | 11,280 | 17,649 | 19,520 | 13,495 | 3,181 | 72,110 |
| 1.6.9 | Plant I, C & Data Systems | 93,031 | 57,166 | 1,496 | 5,672 | 11,576 | 18,113 | 20,034 | 13,850 | 3,264 | 74,006 |
| 1.6.10 | Maintenance & GPE | 13,931 | 2,989 | 78 | 297 | 605 | 947 | 1,047 | 724 | 171 | 3,870 |
| 1.6 | Plant Systems | 673,484 | 365,667 | 9,585 | 36,335 | 74,157 | 115,964 | 128,105 | 88,397 | 20,810 | 471,801 |

| LINE ITEM | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | | |
|----------------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|-----------|--|
| As Spent \$k April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | | |
| WBS TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL | |
| 1.7.1 Administrative Support | | | | | | | | | | 0 | |
| 1.7.2 Management & Planning | | | | | | | | | | 0 | |
| 1.7.3 Maintenance | | | | | | | | | | 0 | |
| 1.7.4 Health&Safety | | | | | | | | | | 0 | |
| 1.7.5 Training | | | | | | | | | | 0 | |
| 1.7.6 QA | | | | | | | | | | 0 | |
| 1.7.7 Utilities | | | | | | | | | | 0 | |
| 1.7.8 Fuel | | | | | | | | | | 0 | |
| 1.7.9 Replacing Equipt & Mods | | | | | | | | | | 0 | |
| 1.7.10 Security | | | | | | | | | | 0 | |
| 1.7.11 Reactor Operations | | | | | | | | | | 0 | |
| 1.7.12 Rsrch Operations | | | | | | | | | | 0 | |
| 1.7.13 Initial Purchases | 8,256 | 7,020 | 285 | 142 | 0 | 639 | 2,655 | 2,065 | 3,426 | 9,211 | |
| 1.7 Operations | 8,256 | 7,020 | 285 | 142 | 0 | 639 | 2,655 | 2,065 | 3,426 | 9,211 | |
| 1.8.1 DOE Support Subcontractng | 6,530 | 5,079 | 133 | 504 | 1,029 | 1,609 | 1,780 | 1,231 | 290 | 6,575 | |
| 1.8 DOE Support | 6,530 | 5,079 | 133 | 504 | 1,029 | 1,609 | 1,780 | 1,231 | 290 | 6,575 | |
| TOTAL | 1,737,989 | 1,039,255 | 32,995 | 120,859 | 240,236 | 353,334 | 346,087 | 195,674 | 46,455 | 1,334,086 | |

| OPERATING EXPENSE | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|-------------------|-----------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|--------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.1.1 | Reactor Core Development | 13,227 | 5,034 | 1,286 | 1,392 | 1,274 | 1,076 | 669 | 409 | 64 | 6,169 |
| 1.1.2 | Fuel Development | 9,658 | 8,297 | 2,162 | 3,485 | 2,749 | 1,112 | 215 | 161 | 83 | 9,966 |
| 1.1.3 | Corrosion Tests & Analysis | 2,415 | 1,193 | 669 | 585 | 135 | 0 | 0 | 0 | 0 | 1,389 |
| 1.1.4 | Core Flow Tests | 31,761 | 11,084 | 1,924 | 1,896 | 2,425 | 3,869 | 3,696 | 0 | 0 | 13,810 |
| 1.1.5 | Control Concepts | 309 | 379 | 126 | 158 | 164 | 0 | 0 | 0 | 0 | 449 |
| 1.1.6 | Critical Experiments | 6,741 | 8,249 | 311 | 2,667 | 2,390 | 3,024 | 1,864 | 0 | 0 | 10,255 |
| 1.1.7 | Matrls Data, Tests and Anly | 15,177 | 15,411 | 3,895 | 7,504 | 3,929 | 2,320 | 455 | 330 | 50 | 18,484 |
| 1.1.8 | Cold Source Development | 5,756 | 6,234 | 1,127 | 2,411 | 2,012 | 1,275 | 373 | 251 | 147 | 7,595 |
| 1.1.9 | Beam Tube, Guide, Inst Dev | 12,925 | 13,007 | 1,030 | 2,099 | 3,903 | 4,336 | 3,198 | 1,243 | 627 | 16,436 |
| 1.1.10 | Hot Source Development | 2,714 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.11 | Neutron Tranport & Shldng | 586 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.12 | I&C System Development | 1,951 | 1,806 | 644 | 806 | 377 | 321 | 0 | 0 | 0 | 2,147 |
| 1.1.13 | Facility Concepts | 10,102 | 9,951 | 3,961 | 2,802 | 1,416 | 1,137 | 1,707 | 863 | 201 | 12,088 |
| 1.1 | Research & Development | 113,322 | 80,645 | 17,136 | 25,804 | 20,773 | 18,469 | 12,177 | 3,257 | 1,172 | 98,789 |
| 1.2.1 | Proj Mgmt & Adminstn | 9,778 | 5,412 | 1,068 | 1,670 | 1,397 | 1,293 | 886 | 246 | 92 | 6,651 |
| 1.2.2 | Systems Engineering | | | | | | | | | | |
| 1.2.3 | Safety | 15,612 | 15,612 | 409 | 1,549 | 3,161 | 4,947 | 5,471 | 3,782 | 891 | 20,211 |
| 1.2.4 | Envrt & Waste Mgmt | 3,080 | 1,780 | 1,238 | 818 | | | | | | 2,056 |
| 1.2.5 | Quality Assurance | 3,034 | 2,428 | 56 | 220 | 466 | 759 | 872 | 626 | 153 | 3,152 |
| 1.2.6 | Training | | | | | | | | | | 0 |
| 1.2.7 | Test & Evaluation | | | | | | | | | | 0 |
| 1.2 | Project Support | 31,504 | 25,232 | 2,770 | 4,257 | 5,024 | 6,999 | 7,229 | 4,653 | 1,136 | 32,069 |
| 1.3.1 | Reactor Assembly | | | | | | | | | | |
| 1.3.2 | Refueling | | | | | | | | | | |
| 1.3.3 | Reactor I&C | | | | | | | | | | |
| 1.3.4 | Fuel | | | | | | | | | | |
| 1.3.5 | Reactor Mockup | | | | | | | | | | |
| 1.3.6 | Maintenance | | | | | | | | | | |
| 1.3 | Reactor Systems | | | | | | | | | | |

| OPERATING EXPENSE | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|-------------------|---------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|--------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.4.1 | Neutron Transport | | | | | | | | | | |
| 1.4.2 | Neutron Scat Inst | 23,962 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.4.3 | Nuc & Fund Physics | 3,938 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.4.4 | Trans U Production | | | | | | | | | | |
| 1.4.5 | Materials Irrad. Facility | | | | | | | | | | |
| 1.4.6 | Isotope Prodt'n Facility | | | | | | | | | | |
| 1.4.7 | Analytical Chem Fac | 2,855 | 345 | | 13 | 51 | 104 | 143 | 113 | 30 | 454 |
| 1.4.8 | Instrument Supprt Fac | | | | | | | | | | |
| 1.4.9 | Comptr & Data Hndlg | | | | | | | | | | |
| 1.4.10 | Cold Source | | | | | | | | | | |
| 1.4.11 | Hot Source | | | | | | | | | | |
| 1.4 | Experiment Systems | 30,755 | 345 | 0 | 13 | 51 | 104 | 143 | 113 | 30 | 454 |
| 1.5.1 | Land Improvements | | | | | | | | | | |
| 1.5.2 | Reactor Building | | | | | | | | | | |
| 1.5.3 | React/Opns Suppt | | | | | | | | | | |
| 1.5.4 | GHal/Res Suppt | | | | | | | | | | |
| 1.5.5 | Office/Interface Bldg | | | | | | | | | | |
| 1.5.6 | Detritiation Building | | | | | | | | | | |
| 1.5.7 | Other Structures | | | | | | | | | | |
| 1.5.8 | Construction Support | | | | | | | | | | |
| 1.5 | Site & Buildings | | | | | | | | | | |
| 1.6.0 | Plant Systems Integration | | | | | | | | | | |
| 1.6.1 | Reactor Water Systems | | | | | | | | | | |
| 1.6.2 | Elec & Comm Systems | | | | | | | | | | |
| 1.6.3 | Environmental Systems | | | | | | | | | | |
| 1.6.4 | Plant Water Systems | | | | | | | | | | |
| 1.6.5 | Plant Service Systems | | | | | | | | | | |
| 1.6.6 | Plant Fire Protection | | | | | | | | | | |
| 1.6.7 | Plant Waste Systems | | | | | | | | | | |
| 1.6.8 | Heavy Water Dtrn & Upgd | | | | | | | | | | |
| 1.6.9 | Plant I, C & Data Systems | 19,914 | 11,116 | | 1,037 | 4,229 | 6,377 | 2,390 | | | 14,034 |
| 1.6.10 | Maintenance & GPE | | | | | | | | | | |
| 1.6 | Plant Systems | 19,914 | 11,116 | 0 | 1,037 | 4,229 | 6,377 | 2,390 | 0 | 0 | 14,034 |

| OPERATING EXPENSE | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|-------------------|----------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|---------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.7.1 | Administrative Support | 7,514 | 3,708 | 50 | 104 | 217 | 395 | 820 | 1,701 | 1,764 | 5,052 |
| 1.7.2 | Management & Planning | 11,343 | 10,674 | 368 | 573 | 1,588 | 2,273 | 2,577 | 3,340 | 3,463 | 14,181 |
| 1.7.3 | Maintenance | 12,319 | 6,868 | 0 | 0 | 0 | 470 | 489 | 1,715 | 6,975 | 9,649 |
| 1.7.4 | Health&Safety | 9,058 | 6,163 | 278 | 288 | 374 | 623 | 1,620 | 2,521 | 2,614 | 8,317 |
| 1.7.5 | Training | 6,825 | 1,623 | 0 | 14 | 60 | 181 | 377 | 782 | 811 | 2,225 |
| 1.7.6 | QA | 9,368 | 8,680 | 109 | 278 | 771 | 1,069 | 2,830 | 3,271 | 3,392 | 11,720 |
| 1.7.7 | Utilities | 3,687 | 8,476 | 0 | 0 | 0 | 778 | 889 | 922 | 9,317 | 11,907 |
| 1.7.8 | Fuel | 30,224 | 10,233 | 0 | 0 | 0 | 0 | 3,019 | 10,956 | 0 | 13,975 |
| 1.7.9 | Replacing Equipt & Mods | | 1,000 | 0 | 0 | 0 | 319 | 332 | 344 | 357 | 1,352 |
| 1.7.10 | Security | 1,585 | 1,232 | 75 | 104 | 135 | 169 | 234 | 303 | 628 | 1,647 |
| 1.7.11 | Reactor Operations | 48,904 | 25,596 | 0 | 0 | 979 | 2,904 | 7,285 | 11,727 | 12,160 | 35,055 |
| 1.7.12 | Rsrch Operations | 74,086 | 32,599 | 0 | 0 | 0 | 3,787 | 7,868 | 16,318 | 16,922 | 44,894 |
| 1.7.13 | Initial Purchases | | 2,400 | 285 | 295 | 147 | 0 | 664 | 2,753 | 2,141 | 6,285 |
| 1.7 | Operations | 214,914 | 119,252 | 1,164 | 1,656 | 4,272 | 12,969 | 29,002 | 56,653 | 60,544 | 166,261 |
| 1.8.1 | DOE Support Subcontracting | 457 | 356 | 9 | 35 | 72 | 113 | 125 | 86 | 20 | 461 |
| 1.8 | DOE Support | 457 | 356 | 9 | 35 | 72 | 113 | 125 | 86 | 20 | 461 |
| TOTAL | | 410,865 | 236,945 | 21,080 | 32,803 | 34,422 | 45,031 | 51,067 | 64,763 | 62,901 | 312,067 |

| CAPITAL EQUIPMENT | | ANS | HIFIR-CNR | Distribution of Costs by Year | | | | | | | |
|-------------------|-----------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|--------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.1.1 | Reactor Core Development | 432 | 430 | 205 | 0 | 0 | 319 | 0 | 0 | 0 | 524 |
| 1.1.2 | Fuel Development | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.3 | Corrosion Tests & Analysis | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.4 | Core Flow Tests | 7,626 | 10,591 | 0 | 3,212 | 6,998 | 2,772 | 0 | 0 | 0 | 12,982 |
| 1.1.5 | Control Concepts | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.6 | Critical Experiments | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.7 | Matrix Data, Tests and Anly | 3,035 | 2,215 | 1,037 | 722 | 0 | 650 | 244 | 0 | 0 | 2,653 |
| 1.1.8 | Cold Source Development | 100 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.9 | Beam Tube, Guide, Inst Dev | 1,060 | 1,065 | 0 | 0 | 0 | 945 | 431 | 0 | 0 | 1,377 |
| 1.1.10 | Hot Source Development | 3,878 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.11 | Neutron Transport & Shldng | 105 | 103 | 55 | 0 | 0 | 70 | 0 | 0 | 0 | 125 |
| 1.1.12 | I&C System Development | 770 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1.1.13 | Facility Concepts | 2,001 | 1,100 | 305 | 56 | 646 | 331 | 0 | 0 | 0 | 1,337 |
| 1.1 | Research & Development | 19,007 | 15,504 | 1,601 | 3,989 | 7,644 | 5,089 | 676 | 0 | 0 | 18,998 |
| 1.2.1 | Proj Mgmt & Adminstrn | | | | | | | | | | |
| 1.2.2 | Systems Engineering | | | | | | | | | | |
| 1.2.3 | Safety | | | | | | | | | | |
| 1.2.4 | Envrt & Waste Mgmt | | | | | | | | | | |
| 1.2.5 | Quality Assurance | | | | | | | | | | |
| 1.2.6 | Training | | | | | | | | | | |
| 1.2.7 | Test & Evaluation | | | | | | | | | | |
| 1.2 | Project Support | | | | | | | | | | |
| 1.3.1 | Reactor Assembly | | | | | | | | | | |
| 1.3.2 | Refueling | | | | | | | | | | |
| 1.3.3 | Reactor I&C | | | | | | | | | | |
| 1.3.4 | Fuel | | | | | | | | | | |
| 1.3.5 | Reactor Mockup | | | | | | | | | | |
| 1.3.6 | Maintenance | | | | | | | | | | |
| 1.3 | Reactor Systems | | | | | | | | | | |

| CAPITAL EQUIPMENT | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|-------------------|---------------------------|----------------|----------------|-------------------------------|---------|---------|---------|---------|---------|---------|-------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.4.1 | Neutron Transport | | | | | | | | | | |
| 1.4.2 | Neutron Scat Inst | | | | | | | | | | |
| 1.4.3 | Nuc & Fund Physics | | | | | | | | | | |
| 1.4.4 | Trans U Production | | | | | | | | | | |
| 1.4.5 | Materials Irrad. Facility | | | | | | | | | | |
| 1.4.6 | Isotope Prodn Facility | | | | | | | | | | |
| 1.4.7 | Analytical Chem Fac | | | | | | | | | | |
| 1.4.8 | Instrument Supprt Fac | | | | | | | | | | |
| 1.4.9 | Comptr & Data Hndlg | | | | | | | | | | |
| 1.4.10 | Cold Source | | | | | | | | | | |
| 1.4.11 | Hot Source | | | | | | | | | | |
| 1.4 | Experiment Systems | | | | | | | | | | |
| 1.5.1 | Land Improvements | | | | | | | | | | |
| 1.5.2 | Reactor Building | | | | | | | | | | |
| 1.5.3 | React/Opns Suppt | | | | | | | | | | |
| 1.5.4 | GHall/Res Suppt | | | | | | | | | | |
| 1.5.5 | Office/Interface Bldg | | | | | | | | | | |
| 1.5.6 | Detritiation Building | | | | | | | | | | |
| 1.5.7 | Other Structures | | | | | | | | | | |
| 1.5.8 | Construction Support | | | | | | | | | | |
| 1.5 | Site & Buildings | | | | | | | | | | |
| 1.6.0 | Plant Systems Integration | | | | | | | | | | |
| 1.6.1 | Reactor Water Systems | | | | | | | | | | |
| 1.6.2 | Elec & Comm Systems | | | | | | | | | | |
| 1.6.3 | Environmental Systems | | | | | | | | | | |
| 1.6.4 | Plant Water Systems | | | | | | | | | | |
| 1.6.5 | Plant Service Systems | | | | | | | | | | |
| 1.6.6 | Plant Fire Protection | | | | | | | | | | |
| 1.6.7 | Plant Waste Systems | | | | | | | | | | |
| 1.6.8 | Heavy Water Dtrn & Upgd | | | | | | | | | | |
| 1.6.9 | Plant I, C & Data Systems | | | | | | | | | | |
| 1.6.10 | Maintenance & GPE | | | | | | | | | | |
| 1.6 | Plant Systems | | | | | | | | | | |

| CAPITAL EQUIPMENT | | ANS | HFIR-CNR | Distribution of Costs by Year | | | | | | | |
|-------------------|---------------------------|----------------|----------------|-------------------------------|--------------|--------------|--------------|--------------|------------|------------|---------------|
| As Spent \$k | April 1994 Baseline | FY 1992 | FY 1992 | Actual Year \$k | | | | | | | |
| WBS | TITLE | (\$K) Total | (\$K) Total | FY 1996 | FY 1997 | FY 1998 | FY 1999 | FY 2000 | FY 2001 | FY 2002 | TOTAL |
| 1.7.1 | Administrative Support | | | | | | | | | | |
| 1.7.2 | Management & Planning | | | | | | | | | | |
| 1.7.3 | Maintenance | | | | | | | | | | |
| 1.7.4 | Health&Safety | | | | | | | | | | |
| 1.7.5 | Training | | | | | | | | | | |
| 1.7.6 | QA | | | | | | | | | | |
| 1.7.7 | Utilities | | | | | | | | | | |
| 1.7.8 | Fuel | | | | | | | | | | |
| 1.7.9 | Replacing Equipt & Mods | | | | | | | | | | |
| 1.7.10 | Security | | | | | | | | | | |
| 1.7.11 | Reactor Operations | 1,256 | 1,194 | | | | 229 | 431 | 468 | 500 | 1,628 |
| 1.7.12 | Rsrch Operations | 1,256 | 1,194 | | | | 229 | 431 | 468 | 500 | 1,628 |
| 1.7.13 | Initial Purchases | | | | | | | | | | |
| 1.7 | Operations | 2,511 | 2,388 | 0 | 0 | 0 | 457 | 863 | 936 | 999 | 3,256 |
| 1.8.1 | DOE Support Subcontractng | 43 | 43 | 24 | | 26 | | | | | 51 |
| 1.8 | DOE Support | 43 | 43 | 24 | 0 | 26 | 0 | 0 | 0 | 0 | 51 |
| TOTAL | | 21,561 | 17,935 | 1,626 | 3,989 | 7,670 | 5,546 | 1,539 | 936 | 999 | 22,305 |

Appendix C

HFIR-CNR SCHEDULE

Individual systems were evaluated for the effect on the schedule of the following:

- reducing the plant power,
- reducing the number of experiments, and
- eliminating several facilities such as the office building, the maintenance support building, and the mockup building.

The project milestones and the schedule by WBS level 3 are indicated in the schedule in this appendix. Reducing the main plant schedule by approximately 25% is appropriate, based on reducing the size of the major facility approximately 33%. Specific reductions and assumptions are summarized in Appendix A.

Other schedule considerations:

1. Regulatory restrictions on the schedule were eliminated based on establishing a close working relationship and continuous oversight rather than summary reviews at the end of the design.
2. Schedule ties between the main facility and the reactor mockup have been broken because the mockup will not be used to validate reactor vessel components before plant start-up. (It will not be used to validate the reflector vessel configuration; rather, it will be fabricated to the design and the mockup built in parallel for configuration validation after installation of the vessel.)
3. Schedule ties between the main facility and the detritiation facility have been broken because the heavy water will be processed at a non-ANS facility and provided "clean" to ANS.
4. Any contamination on the site or relocation of the waste line will be assumed to be cleaned up by another project before site clearing.

| ACTIVITY ID | ACTIVITY DESCRIPTION | ORIG DUR | EARLY START | EARLY FINISH | PROJECT MILESTONES | | | | | | | | | |
|-------------|-------------------------------------|----------|-------------|--------------|---|------|------|------|------|------|------|------|------|--|
| | | | | | FY95 | FY96 | FY97 | FY98 | FY99 | FY00 | FY01 | FY02 | FY03 | |
| 100001 | SCHEDULE START | 0 | 20CT85 | | | | | | | | | | | |
| 100014 | CONTINUE R AND O | 0 | 20CT85 | | | | | | | | | | | |
| 100016 | PROJECT AUTHORIZATION/BEGIN TITLE I | 0 | 20CT85 | | | | | | | | | | | |
| 100018 | INDUSTRIAL TEAM IN PLACE | 0 | 20CT85 | | | | | | | | | | | |
| 100017 | BEGIN EARLY TITLE II DESIGN | 0 | 5DEC88 | | | | | | | | | | | |
| 100022 | BEGIN PROJECT TITLE II DESIGN | 0 | 15OCT87 | | | | | | | | | | | |
| 100020 | BEGIN LONG LEAD PROCUREMENT | 0 | 4JUN88 | | | | | | | | | | | |
| 100021 | ISSUE PSAR | 0 | 20CT87 | | | | | | | | | | | |
| 100024 | START CONSTRUCTION NON-NUCLEAR | 0 | 12DEC87 | | | | | | | | | | | |
| 100023 | BEGIN TVA FEEDER DESIGN | 0 | 10CT88 | | | | | | | | | | | |
| 100028 | COMPLETE TITLE I DESIGN | 0 | 31AUG88 | | | | | | | | | | | |
| 100049 | DOE REVIEW OF PSAR COMPLETE | 0 | 7OCT88 | | | | | | | | | | | |
| 100045 | FIRST NUCLEAR CONCRETE | 0 | 3NOV88 | | | | | | | | | | | |
| 100047 | COMPLETE TITLE II DESIGN | 0 | 24DEC88 | | | | | | | | | | | |
| 100280 | COMPL INSTALATION REFLECTOR VESSEL | 0 | 17OCT89 | | | | | | | | | | | |
| 100055 | COLD SOURCE TIMBLE INSTALLED | 0 | 18JAN91 | | | | | | | | | | | |
| 100091 | ISSUE FSAR | 0 | 18JAN91 | | | | | | | | | | | |
| 100082 | MAJOR SYSTEMS TESTS COMPLETE | 0 | 18MAY92 | | | | | | | | | | | |
| 100084 | DOE APPROVE FSAR/LOW POWER LICENSE | 0 | 18JAN92 | | | | | | | | | | | |
| 100071 | DOE AUTHORIZATION TO LOAD FUEL | 0 | 17JAN92 | | | | | | | | | | | |
| 100072 | PROCUREMENT COMPLETE | 0 | 17OCT91 | | | | | | | | | | | |
| 100075 | CORE LOAD | 0 | 14FEB92 | | | | | | | | | | | |
| 100080 | INITIAL CRITICALITY | 0 | 18MAY92 | | | | | | | | | | | |
| 100087 | LOW POWER TESTING COMPLETE | 0 | 6SEP92 | | | | | | | | | | | |
| 100088 | OPERATIONAL TESTING COMPLETE | 0 | 28SEP92 | | | | | | | | | | | |
| 100079 | PROJECT COMPLETE | 0 | 28SEP92 | | | | | | | | | | | |
| 120108 | CONSTRUCTION WRT SUPPORT | 1828 | 20CT85 | 28SEP92 | 1.2.1 - PROJECT MANAGEMENT & ADMINISTRATION | | | | | | | | | |
| 120201 | FUEL STORAGE DESIGN/CONFIGURATION W | 1182 | 20CT85 | 14MAR90 | 1.2.2 - SYSTEMS ENGINEERING | | | | | | | | | |
| 120202 | CONSTRUCTION PLANNING | 522 | 20CT85 | 30SEP87 | | | | | | | | | | |
| 120203 | SYSTEMS INTEGRATION | 1828 | 20CT85 | 30SEP92 | | | | | | | | | | |
| 120204 | SYSTEMS REQUIREMENTS | 1121 | 20CT85 | 17JAN90 | | | | | | | | | | |
| 120205 | SYSTEMS DESCRIPTIONS | 1200 | 20CT85 | 29JUL88 | | | | | | | | | | |
| 120212 | OTHER CONSTRUCTION SUPPORT | 1177 | 20CT85 | 5APR91 | | | | | | | | | | |
| 120301 | SAFETY CRIT REVIEW AND DEVELOPMENT | 1220 | 20CT85A | 2JUN92 | 1.2.3 - SAFETY | | | | | | | | | |
| 120302 | ACCIDENT ANALYSIS | 1828 | 20CT85 | 28SEP92 | | | | | | | | | | |

C-3

Plot Date: 11MAR93
 Date Data: 20CT85
 Project Start: 1APR93
 Project Finish: 20CT87

Scale: 1" = 1 Year
 Legend: Milestones
 Activity Duration

DOE / MARTIN MARIETTA ENERGY SYSTEMS
 CENTER FOR NEUTRON RESEARCH
 ACCELERATED SCHEDULE

| Date | Revision | Checked | Approved |
|------|----------|---------|----------|
| | | | |
| | | | |
| | | | |

(C) Princeton Systems, Inc.

| ACTIVITY ID | ACTIVITY DESCRIPTION | ORIG DUR | EARLY START | EARLY FINISH | Fiscal Year | | | | | | | | |
|-------------|-------------------------------------|----------|-------------|--------------|--|------|------|------|------|------|------|------|------|
| | | | | | FY95 | FY96 | FY97 | FY98 | FY99 | FY00 | FY01 | FY02 | FY03 |
| 120303 | SAFETY ANALYSIS REPORT(SAR) | 1428 | 20OCT98 | 20SEP02 | 1.2.3 - SAFETY | | | | | | | | |
| 120304 | PROBABALISTIC RISK ASSESSMENT (PRA) | 1821 | 20OCT98 | 20SEP02 | | | | | | | | | |
| 120305 | SEVERE ACCIDENT ANALYSIS | 1821 | 20OCT98 | 20SEP02 | | | | | | | | | |
| 120308 | SAFETY REVIEWS | 1008 | 20OCT98 | 20JUL99 | | | | | | | | | |
| 120401 | ENVIRONMENTAL PLANNING | 1483 | 4JAN93A | 14AUG98 | 1.2.4 - ENVIRONMENTAL & WASTE MANAGEMNT PLANNING | | | | | | | | |
| 120402 | WASTE MANAGEMENT PLANNING | 1300 | 10OCT97 | 20OCT02 | | | | | | | | | |
| 120412 | OTHER SYSTEMS ENGR SUPPORT | 2480 | 20MAR93A | 20SEP02 | | | | | | | | | |
| 120510 | TRAINING | 1828 | 20OCT98 | 20SEP02 | 1.2.6 - TRAINING | | | | | | | | |
| 120701 | TEST & EVALUATION PLANNING | 1000 | 20OCT98 | 20JUL99 | 1.2.7 - TEST & EVALUATION | | | | | | | | |
| 120702 | TEST & EVALUATION PLANNING | 890 | 18AUG99 | 28NOV01 | | | | | | | | | |
| 130101 | TITLE I ENGINEERING | 821 | 20OCT98 | 28SEP97 | 1.3.1 - REACTOR ASSEMBLY | | | | | | | | |
| 130102 | TITLE II ENGINEERING | 810 | 8APR97 | 28SEP00 | | | | | | | | | |
| 130103 | BID AND AWARD | 770 | 8APR98 | 10JAN01 | | | | | | | | | |
| 130104 | VENDOR DESIGN | 770 | 10SEP98 | 22AUG01 | | | | | | | | | |
| 130105 | VENDOR FABRICATION | 880 | 15JUL99 | 17OCT01 | | | | | | | | | |
| 130108 | CONSTR AND FIELD ENGR SUP | 418 | 17JUL00 | 15FEB02 | | | | | | | | | |
| 130201 | TITLE I ENGINEERING | 821 | 20OCT98 | 28SEP97 | 1.3.2 - REFUELING | | | | | | | | |
| 130202 | TITLE II ENGINEERING | 481 | 27MAR97 | 17DEC98 | | | | | | | | | |
| 130203 | BID AND AWARD | 822 | 20DEC97 | 12JAN00 | | | | | | | | | |
| 130204 | VENDOR DESIGN | 488 | 1MAY98 | 11FEB00 | | | | | | | | | |
| 130205 | VENDOR FABRICATION | 820 | 21JUL98 | 24JUL00 | | | | | | | | | |
| 130206 | CONSTR AND FIELD ENGR SUP | 352 | 22DEC98 | 27APR01 | | | | | | | | | |
| 130207 | CONSTRUCTION TESTING | 104 | 20APR01 | 20SEP01 | | | | | | | | | |
| 130208 | STARTUP TESTING | 104 | 21SEP01 | 13FEB02 | | | | | | | | | |
| 130401 | TITLE I ENGINEERING | 382 | 20OCT98 | 2APR97 | 1.3.4 - FUEL ASSEMBLY | | | | | | | | |
| 130402 | TITLE II ENGINEERING | 482 | 10OCT97 | 16APR98 | | | | | | | | | |
| 130403 | BID AND AWARD | 192 | 18APR98 | 28NOV98 | | | | | | | | | |
| 130405 | VENDOR FABRICATION | 820 | 28NOV98 | 22NOV01 | | | | | | | | | |
| 130501 | TITLE I ENGINEERING | 821 | 20OCT98 | 28SEP97 | 1.3.5 - REACTOR ASSEMBLY MOCKUP | | | | | | | | |
| 130502 | TITLE II ENGINEERING | 382 | 22SEP97 | 1FEB99 | | | | | | | | | |

C-4

Prep Date: 14MAR98
 Data Date: 20CT98
 Project Start: 1APR98
 Project Finish: 20CT02

 Activity Description:
 Control Activity:
 Directed by Activity:
 LY80

DOE / MARTIN MARIETTA ENERGY SYSTEMS
 CENTER FOR NEUTRON RESEARCH
 ACCELERATED SCHEDULE

Page 1 of 1

| Date | Revised | Checked | Approved |
|----------|---------|---------|----------|
| 12/16/94 | | | |
| | | | |
| | | | |

(C) Martin Marietta Energy Systems, Inc.

| ACTIVITY ID | ACTIVITY DESCRIPTION | ORIG DUR | EARLY START | EARLY FINISH | | | | | | | | | |
|-------------|----------------------------|----------|-------------|--------------|--|------|------|------|------|------|------|------|------|
| | | | | | FY95 | FY96 | FY97 | FY98 | FY99 | FY00 | FY01 | FY02 | FY03 |
| | | | | | 1.3.5 - REACTOR ASSEMBLY MOCKUP | | | | | | | | |
| 130523 | BID AND AWARD | 120 | 10OCT98 | 18MAR99 | | | | | | | | | |
| 130524 | VENDOR DESIGN | 140 | 22MAR99 | 10OCT99 | | | | | | | | | |
| 130525 | VENDOR FABRICATION | 140 | 22MAR99 | 10OCT99 | | | | | | | | | |
| 130508 | CONSTR AND FIELD ENGR SUP | 480 | 4OCT98 | 3AUG01 | | | | | | | | | |
| 130509 | STARTUP TESTING | 525 | 4JAN00 | 7JAN02 | | | | | | | | | |
| | | | | | 1.4.1 - NEUTRON BEAM TRANSPORT | | | | | | | | |
| 140101 | TITLE I ENGINEERING | 521 | 20OCT95 | 27SEP97 | | | | | | | | | |
| 140102 | TITLE II ENGINEERING | 700 | 30SEP97 | 5JUN00 | | | | | | | | | |
| 140103 | BID AND AWARD | 780 | 2APR98 | 2MAR99 | | | | | | | | | |
| 140104 | VENDOR DESIGN | 810 | 4OCT98 | 11NOV99 | | | | | | | | | |
| 140105 | VENDOR FABRICATION | 788 | 7OCT97 | 16OCT99 | | | | | | | | | |
| 140106 | CONSTR AND FIELD ENGR SUP | 878 | 14APR99 | 6MAY01 | | | | | | | | | |
| 140107 | CONSTRUCTION TESTING | 398 | 4DEC98 | 18JUN02 | | | | | | | | | |
| 140108 | STARTUP TESTING | 130 | 11MAR02 | 19SEP02 | | | | | | | | | |
| | | | | | 1.4.2 - NEUTRON SCATTERING INSTRUMENTS | | | | | | | | |
| 140201 | TITLE I ENGINEERING | 521 | 20OCT95 | 27SEP97 | | | | | | | | | |
| 140202 | TITLE II ENGINEERING | 818 | 30SEP97 | 17APR01 | | | | | | | | | |
| 140203 | BID AND AWARD | 817 | 4JUL99 | 7JAN00 | | | | | | | | | |
| 140204 | VENDOR DESIGN | 1139 | 8JAN97 | 15APR01 | | | | | | | | | |
| 140205 | VENDOR FABRICATION | 788 | 8JAN99 | 28JAN01 | | | | | | | | | |
| 140206 | CONSTR AND FIELD ENGR SUP | 388 | 2JAN01 | 28FEB02 | | | | | | | | | |
| 140207 | CONSTRUCTION TESTING | 388 | 6APR01 | 28MAY02 | | | | | | | | | |
| 140208 | STARTUP TESTING | 132 | 21MAR02 | 30SEP02 | | | | | | | | | |
| | | | | | 1.4.10 - COLD SOURCE ASSEMBLIES | | | | | | | | |
| 141001 | TITLE I ENGINEERING | 781 | 20OCT95 | 21AUG97 | | | | | | | | | |
| 141002 | TITLE II ENGINEERING | 877 | 9OCT97 | 24DEC99 | | | | | | | | | |
| 141003 | BID AND AWARD | 824 | 8JAN99 | 12JAN99 | | | | | | | | | |
| 141004 | VENDOR DESIGN | 480 | 16JUL99 | 17APR00 | | | | | | | | | |
| 141005 | VENDOR FABRICATION | 488 | 16APR99 | 8MAR01 | | | | | | | | | |
| 141006 | CONSTR AND FIELD ENGR SUP | 316 | 24APR00 | 8JUL01 | | | | | | | | | |
| 141008 | STARTUP TESTING | 118 | 8APR01 | 7SEP01 | | | | | | | | | |
| 141009 | FINAL STARTUP/PHOP TESTING | 132 | 10SEP01 | 12MAR02 | | | | | | | | | |
| | | | | | 1.5.1 - LAND IMPROVEMENTS | | | | | | | | |
| 150101 | TITLE I ENGINEERING | 408 | 20OCT95 | 15APR97 | | | | | | | | | |
| 150102 | TITLE II ENGINEERING | 781 | 12MAR97 | 18NOV99 | | | | | | | | | |
| 150103 | VENDOR FABRICATION | 210 | 21SEP99 | 23AUG00 | | | | | | | | | |
| 150108 | CONSTR AND FIELD ENGR SUP | 880 | 12DEC97 | 28APR01 | | | | | | | | | |
| 150112 | OTHER ENGR SUPPORT | 128 | 20OCT95 | 18OCT99 | | | | | | | | | |

CS

| | | | |
|---|---|---|--|
| Plan Date: 14MAR99 Date Drawn: 20C196 Project Start: 1APR99 Project Finish: 20C192 | Activity Summary Item: 1700 Control Limit by: Review-off by Activity: | DOE / MARTIN MARIETTA ENERGY SYSTEMS CENTER FOR NEUTRON RESEARCH ACCELERATED SCHEDULE | Date: 12/15/04 Reviewer: Checker: Approver: |
|---|---|---|--|

| ACTIVITY ID | ACTIVITY DESCRIPTION | ORIG DUR | EARLY START | EARLY FINISH | | | | | | | | | | |
|---|---------------------------|----------|-------------|--------------|------|------|------|------|------|------|------|------|------|--|
| | | | | | FY95 | FY96 | FY97 | FY98 | FY99 | FY00 | FY01 | FY02 | FY03 | |
| 1.5.2 - REACTOR BUILDING | | | | | | | | | | | | | | |
| 150201 | TITLE I ENGINEERING | 491 | 20CT95 | 4AUG97 | | | | | | | | | | |
| 150202 | TITLE II ENGINEERING | 375 | 2APR97 | 25EP98 | | | | | | | | | | |
| 150203 | BID AND AWARD | 352 | 4JUN97 | 10CT98 | | | | | | | | | | |
| 150204 | VENDOR DESIGN | 320 | 10CT97 | 27NOV98 | | | | | | | | | | |
| 150205 | VENDOR FABRICATION | 698 | 2MAR98 | 2NOV00 | | | | | | | | | | |
| 150206 | CONSTR AND FIELD ENGR SUP | 900 | 1MAY98 | 24MAY01 | | | | | | | | | | |
| 150208 | STARTUP TESTING | 15 | 12OCT01 | 1NOV01 | | | | | | | | | | |
| 1.5.3 - REACTOR SUPPORT BUILDING | | | | | | | | | | | | | | |
| 150301 | TITLE I ENGINEERING | 425 | 20CT95 | 18MAY97 | | | | | | | | | | |
| 150302 | TITLE II ENGINEERING | 482 | 18MAY97 | 23MAR99 | | | | | | | | | | |
| 150308 | CONSTR AND FIELD ENGR SUP | 574 | 5NOV98 | 18JAN01 | | | | | | | | | | |
| 1.5.4 - GUIDE HALL / RESEARCH SUPPORT BUILDING | | | | | | | | | | | | | | |
| 150401 | TITLE I ENGINEERING | 416 | 20CT95 | 2MAY97 | | | | | | | | | | |
| 150402 | TITLE II ENGINEERING | 449 | 2APR97 | 10EP98 | | | | | | | | | | |
| 150408 | CONSTR AND FIELD ENGR SUP | 522 | 15EP98 | 21SEP00 | | | | | | | | | | |
| 1.5.5 - INTERFACE BUILDING | | | | | | | | | | | | | | |
| 150501 | TITLE I ENGINEERING | 455 | 20CT95 | 27JUN97 | | | | | | | | | | |
| 150502 | TITLE II ENGINEERING | 324 | 28MAR97 | 24JUN98 | | | | | | | | | | |
| 150508 | CONSTR AND FIELD ENGR SUP | 590 | 21MAY98 | 17JUL00 | | | | | | | | | | |
| 1.5.6 - DETRIITIATION BUILDING | | | | | | | | | | | | | | |
| 150601 | TITLE I ENGINEERING | 418 | 20CT95 | 8MAY97 | | | | | | | | | | |
| 150602 | TITLE II ENGINEERING | 418 | 2JAN97 | 8AUG98 | | | | | | | | | | |
| 150603 | BID AND AWARD | 132 | 5JAN98 | 7JUL98 | | | | | | | | | | |
| 150605 | VENDOR FABRICATION | 299 | 8JUL98 | 13APR99 | | | | | | | | | | |
| 150608 | CONSTR AND FIELD ENGR SUP | 250 | 11FEB99 | 28JAN02 | | | | | | | | | | |
| 1.5.7 - OTHER STRUCTURES | | | | | | | | | | | | | | |
| 150701 | TITLE I ENGINEERING | 395 | 20CT95 | 4APR97 | | | | | | | | | | |
| 150702 | TITLE II ENGINEERING | 822 | 7APR97 | 17OCT99 | | | | | | | | | | |
| 150708 | CONSTR AND FIELD ENGR SUP | 600 | 17OCT98 | 11SEP00 | | | | | | | | | | |
| 1.5.8 - CONSTRUCTION SUPPORT | | | | | | | | | | | | | | |
| 150801 | TITLE I ENGINEERING | 329 | 20CT95 | 2JAN97 | | | | | | | | | | |
| 150802 | TITLE II ENGINEERING | 327 | 2JAN97 | 4APR98 | | | | | | | | | | |
| 150803 | BID AND AWARD | 820 | 20CT98 | 18FEB99 | | | | | | | | | | |
| 150805 | VENDOR FABRICATION | 480 | 4APR97 | 18FEB98 | | | | | | | | | | |
| 150808 | CONSTR AND FIELD ENGR SUP | 1200 | 7OCT97 | 12MAY99 | | | | | | | | | | |
| 1.6.0 - GENERAL PLANT SYSTEMS | | | | | | | | | | | | | | |
| 150901 | TITLE I ENGINEERING | 388 | 20CT95 | 7APR97 | | | | | | | | | | |
| 150902 | TITLE II ENGINEERING | 1233 | 8APR97 | 27DEC98 | | | | | | | | | | |

C-6

Plot Date: 14MAR98
 Date Data: 20C95
 Project Start: 1APR93
 Project Finish: 20CT98

Activity Start/End Dates:
 Control Limit by:
 Interval of the Activity:

1730
 (c) Primavera Systems, Inc.

DOE / MARTIN MARIETTA ENERGY SYSTEMS
 CENTER FOR NEUTRON RESEARCH
 ACCELERATED SCHEDULE

Sheet 1 of 1

| Date | Revision | Checked | Approved |
|------|----------|---------|----------|
| | | | |
| | | | |
| | | | |

12/16/94

| ACTIVITY ID | ACTIVITY DESCRIPTION | ORIG DUR | EARLY START | EARLY FINISH | | | | | | | | | | |
|-------------|---------------------------|----------|-------------|--------------|---|------|------|------|------|------|------|------|------|--|
| | | | | | FY95 | FY96 | FY97 | FY98 | FY99 | FY00 | FY01 | FY02 | FY03 | |
| | | | | | 1.6.1 - REACTOR WATER SYSTEMS | | | | | | | | | |
| 180101 | TITLE I ENGINEERING | 418 | 20CT95 | 7MAY97 | | | | | | | | | | |
| 180102 | TITLE II ENGINEERING | 820 | 8MAY97 | 8OCT99 | | | | | | | | | | |
| 180103 | BID AND AWARD | 124 | 5DEC98 | 27MAY97 | | | | | | | | | | |
| 180104 | VENDOR DESIGN | 147 | 28MAY97 | 18DEC97 | | | | | | | | | | |
| 180105 | VENDOR FABRICATION | 280 | 5APR99 | 12MAY00 | | | | | | | | | | |
| 180106 | CONSTR AND FIELD ENGR SUP | 254 | 15MAY00 | 3MAY01 | | | | | | | | | | |
| 180107 | CONSTRUCTION TESTING | 239 | 15NOV00 | 4MARC02 | | | | | | | | | | |
| 180108 | STARTUP TESTING | 292 | 18MARC01 | 18SEP02 | | | | | | | | | | |
| | | | | | 1.6.2 - PLT ELECTRIC POWER & COMMUNICATIONS SYS | | | | | | | | | |
| 180201 | TITLE I ENGINEERING | 820 | 20CT95 | 27FEB98 | | | | | | | | | | |
| 180202 | TITLE II ENGINEERING | 825 | 8JUN97 | 10DEC99 | | | | | | | | | | |
| 180203 | BID AND AWARD | 477 | 8JAN97 | 1NOV98 | | | | | | | | | | |
| 180204 | VENDOR DESIGN | 280 | 8JUN97 | 8JUN98 | | | | | | | | | | |
| 180205 | VENDOR FABRICATION | 478 | 18SEP97 | 8JUL99 | | | | | | | | | | |
| 180206 | CONSTR AND FIELD ENGR SUP | 592 | 12AUG98 | 18NOV00 | | | | | | | | | | |
| 180207 | CONSTRUCTION TESTING | 371 | 8JAN99 | 18MARC01 | | | | | | | | | | |
| 180208 | STARTUP TESTING | 870 | 12APR99 | 15JUN01 | | | | | | | | | | |
| 180212 | OTHER ENGR SUPPORT | 1086 | 20CT95 | 10DEC98 | | | | | | | | | | |
| | | | | | 1.6.3 - ENVIRONMENTAL SYSTEMS | | | | | | | | | |
| 180301 | TITLE I ENGINEERING | 478 | 20CT95 | 18JUL97 | | | | | | | | | | |
| 180302 | TITLE II ENGINEERING | 488 | 28MAY97 | 12APR99 | | | | | | | | | | |
| 180303 | BID AND AWARD | 477 | 28JAN97 | 28NOV98 | | | | | | | | | | |
| 180304 | VENDOR DESIGN | 478 | 12JUL97 | 28APR99 | | | | | | | | | | |
| 180305 | VENDOR FABRICATION | 440 | 8JUL98 | 18MARC99 | | | | | | | | | | |
| 180306 | CONSTR AND FIELD ENGR SUP | 620 | 14APR99 | 21NOV00 | | | | | | | | | | |
| 180307 | CONSTRUCTION TESTING | 380 | 18OCT99 | 28MARC01 | | | | | | | | | | |
| 180308 | STARTUP TESTING | 320 | 18APR00 | 22JUL01 | | | | | | | | | | |
| | | | | | 1.6.4 - PLANT WATER SYSTEMS | | | | | | | | | |
| 180401 | TITLE I ENGINEERING | 424 | 20CT95 | 28MAY97 | | | | | | | | | | |
| 180402 | TITLE II ENGINEERING | 820 | 28MAY97 | 21OCT99 | | | | | | | | | | |
| 180403 | BID AND AWARD | 827 | 31OCT98 | 28FEB99 | | | | | | | | | | |
| 180404 | VENDOR DESIGN | 227 | 28MAY97 | 12APR98 | | | | | | | | | | |
| 180405 | VENDOR FABRICATION | 320 | 10CT97 | 12OCT99 | | | | | | | | | | |
| 180406 | CONSTR AND FIELD ENGR SUP | 440 | 28JUN99 | 8MARC01 | | | | | | | | | | |
| 180407 | CONSTRUCTION TESTING | 280 | 21MARC00 | 18AUG01 | | | | | | | | | | |
| 180408 | STARTUP TESTING | 140 | 2NOV01 | 18MAY02 | | | | | | | | | | |
| | | | | | 1.6.5 - PLANT SERVICE SYSTEMS | | | | | | | | | |
| 180501 | TITLE I ENGINEERING | 424 | 20CT95 | 28MAY97 | | | | | | | | | | |

C-7

| | | | |
|---|--|--|--|
| Plan Date: 15MAY95 Cost Date: 20CT95 Project Start: 12APR93 Project Finish: 20CT98 | | Army, Navy, Air Force, Defense, State, Energy, and Environmental Protection Department of Energy Martin Marietta Energy Systems Center for Neutron Research Accelerated Schedule | Date: 12/15/99 Reviewer: _____ Checker: _____ Approver: _____ |
|---|--|--|--|

| ACTIVITY ID | ACTIVITY DESCRIPTION | ORIG DUR | EARLY START | EARLY FINISH | | | | | | | | | | |
|-------------|---------------------------|----------|-------------|--------------|---|------|------|------|------|------|------|------|------|--|
| | | | | | FY95 | FY96 | FY97 | FY98 | FY99 | FY00 | FY01 | FY02 | FY03 | |
| | | | | | 1.6.5 - PLANT SERVICE SYSTEMS | | | | | | | | | |
| 180502 | TITLE II ENGINEERING | 378 | 30MAY87 | 18NOV88 | | | | | | | | | | |
| 180503 | BID AND AWARD | 181 | 27DEC88 | 18AUG87 | | | | | | | | | | |
| 180504 | VENDOR DESIGN | 152 | 1MAY87 | 1DEC87 | | | | | | | | | | |
| 180505 | VENDOR FABRICATION | 348 | 8SEP87 | 4JAN88 | | | | | | | | | | |
| 180506 | CONSTR AND FIELD ENGR SUP | 540 | 8SEP88 | 3OCT00 | | | | | | | | | | |
| 180507 | CONSTRUCTION TESTING | 540 | 12MAR89 | 1APR91 | | | | | | | | | | |
| 180508 | STARTUP TESTING | 540 | 14JUN89 | 8JUL01 | | | | | | | | | | |
| | | | | | 1.6.8 - HEAVY WATER DETRIATION & UPGRADE | | | | | | | | | |
| 180801 | TITLE I ENGINEERING | 532 | 2OCT85 | 14OCT87 | | | | | | | | | | |
| 180802 | TITLE II ENGINEERING | 378 | 23OCT87 | 6APR88 | | | | | | | | | | |
| 180803 | BID AND AWARD | 161 | 4JUN88 | 14JAN87 | | | | | | | | | | |
| 180804 | VENDOR DESIGN | 287 | 16JAN87 | 21JAN88 | | | | | | | | | | |
| 180805 | VENDOR FABRICATION | 482 | 23JAN88 | 1NOV88 | | | | | | | | | | |
| 180806 | CONSTR AND FIELD ENGR SUP | 320 | 2NOV88 | 5FEB91 | | | | | | | | | | |
| 180807 | CONSTRUCTION TESTING | 208 | 19SEP89 | 18JUN91 | | | | | | | | | | |
| 180808 | STARTUP TESTING | 122 | 18JUN91 | 18DEC91 | | | | | | | | | | |
| | | | | | 1.6.9 - PLANT INSTRUMENTATION & DATA SYSTEMS | | | | | | | | | |
| 180901 | TITLE I ENGINEERING | 874 | 2OCT85 | 30APR88 | | | | | | | | | | |
| 180902 | TITLE II ENGINEERING | 741 | 1DEC88 | 2OCT88 | | | | | | | | | | |
| 180903 | BID AND AWARD | 788 | 2OCT88 | 8OCT89 | | | | | | | | | | |
| 180904 | VENDOR FABRICATION | 1185 | 3APR87 | 18SEP91 | | | | | | | | | | |
| 180905 | CONSTR AND FIELD ENGR SUP | 781 | 8OCT87 | 4SEP89 | | | | | | | | | | |
| 180907 | CONSTRUCTION TESTING | 1200 | 8OCT87 | 12MAY92 | | | | | | | | | | |
| 180908 | STARTUP TEST | 1200 | 7OCT88 | 18AUG92 | | | | | | | | | | |
| | | | | | 1.7.03 - OPERATION MAINTENANCE | | | | | | | | | |
| 170310 | MAINTENANCE | 1305 | 2OCT85 | 28SEP92 | | | | | | | | | | |
| | | | | | 1.7.05 - OPERATION TRAINING | | | | | | | | | |
| 170510 | TRAINING | 784 | 2AUG88 | 18AUG92 | | | | | | | | | | |
| | | | | | 1.7.06 - OPERATION QUALITY ASSURANCE | | | | | | | | | |
| 170610 | QUALITY ASSURANCE | 1004 | 8OCT88 | 18AUG92 | | | | | | | | | | |
| | | | | | 1.7.07 - OPERATION UTILITIES | | | | | | | | | |
| 170710 | UTILITIES | 182 | 12APR91 | 23SEP92 | | | | | | | | | | |
| | | | | | 1.7.08 - OPERATION FUEL | | | | | | | | | |
| 170810 | FUEL | 829 | 7APR88 | 28SEP92 | | | | | | | | | | |
| | | | | | 1.7.11 - REACTOR OPERATIONS | | | | | | | | | |
| 171110 | REACTOR OPERATIONS | 1580 | 2OCT88 | 24SEP92 | | | | | | | | | | |
| | | | | | 1.7.12 - RESEARCH OPERATIONS | | | | | | | | | |
| 171210 | EXPERIMENT OPERATIONS | 1043 | 2OCT85 | 28SEP88 | | | | | | | | | | |

C8

Prep Date: 11MAY94
 Data Date: 2OCT88
 Project Start: 1APR92
 Project Finish: 2OCT88


 Primary Schedule Dates
 Control Limits by
 Attention of the Agency

1130

DOE / MARTIN MARIETTA ENERGY SYSTEMS
 CENTER FOR NEUTRON RESEARCH
 ACCELERATED SCHEDULE

12/16/94

| Date | Name | Checked | Approved |
|------|------|---------|----------|
| | | | |
| | | | |
| | | | |

Appendix D

SCIENTIFIC INSTRUMENTS

Scientific instruments included in the HFIR-CNR are listed in Table D.1 by WBS number. Also shown is the funding category associated with each instrument. The distribution is consistent with the capabilities of the facility and input from the scientific community.

D.1. Experiment systems instrument list/funding category

| Instrument | Instrument Number | Funding category |
|---|----------------------|---------------------|
| 1.4.2 Neutron scattering instruments | | |
| 1.4.2.1 Single-crystal instruments | | |
| Single-crystal diffractometer | T-1 | Line item |
| Single-crystal diffractometer | T-2 | Line item |
| Polarized single-crystal diffractometer | T-3 | Line item |
| Protein crystal diffractometer | L-10 | Line item |
| 1.4.2.2 Powder diffractometers | | |
| High-resolution powder diffractometer | T-4 | Line item |
| High-intensity powder diffractometer | T-5 | Line item |
| 1.4.2.3 Time-of-flight (TOF) spectrometers | | |
| Time-focusing TOF spectrometer | D-9 | Line item |
| 1.4.2.4 Triple-axis spectrometers | | |
| Triple-axis spectrometer | T-11 | Line item |
| Triple-axis spectrometer | T-12 | Line item |
| Triple-axis spectrometer | D-12 | Line item |
| Triple-axis spectrometer | L-8 | Line item |
| 1.4.2.5 Small-angle neutron scattering (SANS) | | |
| SANS—10 m | L-1 | Line item |
| SANS—20 m (biology) | D-3 | Line item |
| SANS—40 m | D-4 | Line item |
| 1.4.2.7 High-resolution spectroscopy | | |
| Neutron spin echo spectrometer | D-2 | Line item |
| Backscattering spectrometer | L-4 | Line item |
| 1.4.2.8 Neutron optical instruments | | |
| Interferometer | L-7 | Line item |
| Reflectometer | D-13 | Line item |
| 1.4.2.9 Ultracold neutron (UCN) facilities | | |

| Instrument | Instrument Number | Funding category |
|---|-------------------|-------------------|
| UCN turbine converter | V-2 | Line item |
| Neutron storage bottle | U-2 | Operating expense |
| Neutron microscope | U-3 | Operating expense |
| Electric dipole moment | U-4 | Operating expense |
| UCN station | U-5 | Operating expense |
| 1.4.2.10 Development scattering instruments | | |
| General purpose area detector | L-3 | Operating expense |
| 1.4.3 Nuclear and fundamental physics instruments | | |
| 1.4.3.2 Polarized nuclear physics | | |
| Precision gamma-ray bolometer | D-7 | Line item |
| 1.4.7 Analytical chemistry facilities | | |
| 1.4.7.1 Materials analysis facilities | | |
| Prompt-gamma activation analysis multibeam facility | D-16 | Line item |
| Neutron depth profiling facility | C-2 | Line item |
| Gamma irradiation facility | | Operating expense |
| Positron detectors | | Operating expense |

Appendix E

PRINCIPAL CONTRIBUTORS

- | | |
|---|-------------------------------|
| 1. Overall guidance and direction | C. D. West/J. E. Cleaves |
| 1.2 Scientific requirements | J. B. Hayter |
| 1.2 Design summary | F. J. Peretz |
| 2. Overall requirements and key design parameters | |
| 2.1 Plant design requirements | R. S. Booth |
| 2.2 Core design parameters | D. L. Selby/G. L. Yoder |
| 3. Reactor systems | |
| 3.1 Reactor assembly | C. C. Queen Jr. |
| 3.2 Refueling and maintenance | K. K. Chipley |
| 3.3 Reactor control | R. E. Battle |
| 3.4 Fuel element assemblies | C. C. Queen Jr. |
| 4. Experiment systems | |
| 4.1 Neutron beam transport | T. J. McManamy |
| 4.2 Neutron scattering instruments | T. J. McManamy |
| 4.3 Nuclear and fundamental physics instruments | T. J. McManamy |
| 4.4 Transuranium production | T. J. McManamy |
| | A. E. Williams |
| 4.5 Materials irradiation | T. J. McManamy |
| | A. E. Williams |
| 4.6 Isotope production | C. C. Eberle |
| 4.7 Analytical chemistry and positron research | C. C. Eberle |
| 4.10 Cold source | A. Lucas/D. H. Vandergriff |
| 5. Site and buildings | |
| 5.1 General site and buildings | H. B. Shapira |
| | W. W. Bowman/N. E. Stone |
| 5.2 Positron spectroscopy facility | C. C. Eberle |
| 6. Plant systems | |
| 6.1 Reactor water systems | G. R. McNutt |
| 6.2 Electrical and communication systems | M. E. Mathews/J. T. Cleveland |
| 6.3 Environmental control | C. W. Parker |
| 6.4 Plant water systems | J. P. Schubert |
| 6.5 Plant service systems | J. P. Schubert |
| 6.6 Fire protection | J. P. Schubert |
| 6.7 Plant waste systems | J. R. Joplin/W. R. Reed |
| 6.8 Heavy water detritiation and upgrade facility | J. R. DeVore |
| 6.9 Instrumentation and data systems | J. E. Cleaves |
| 7. Operations | M. M. Houser/W. E. Hill |

8. Research and development

D. L. Selby

9. Safety and regulatory compliance

D. L. Moses/R. M. Harrington

10. Quality assurance

M. L. Gildner

11. Summary cost estimate

R. L. Johnson

12. Summary schedule

R. A. Brown

Internal Distribution

1. B. R. Appleton
2. R. E. Battle
3. R. S. Booth
4. W. W. Bowman
5. R. A. Brown
6. J. H. Campbell
7. K.K. Chipley
8. J. E. Cleaves
9. J. T. Cleveland
10. J. R. DeVore
11. C.C. Eberle
12. R. M. Harrington
13. J. B. Hayter
14. W. E. Hill
15. M. M. Houser
16. J. R. Joplin
- 17-20. R. L. Johnson
21. A. Lucas
22. J. A. March-Leuba
23. M. E. Mathews
24. T. J. McManamy
25. G. R. McNutt
26. C. W. Parker
27. F. J. Peretz
28. C. C. Queen
29. W. R. Reed
30. D. L. Selby
31. J. P. Schubert
32. H. B. Shapira
33. N. E. Stone
34. P. B. Thompson
35. D. H. Vandergriff
36. C. D. West
37. A. E. Williams
38. ORNL Patent Office
- 39-40. Document Research Library (2)
41. Y-12 Technical Library
- 42-43. Laboratory Records
44. Laboratory Records (RC)

External Distribution

45. D. K. Wilfert, Energy Programs, U.S. Department of Energy, Oak Ridge Field Office, FEDC, MS-8218, P. O.Box 2009, Oak Ridge, TN 37831-8218.
46. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831.

